

**BINGHAMTON**  
**UNIVERSITY**  
STATE UNIVERSITY OF NEW YORK

PHYSICAL FACILITIES

PO Box 6000  
BINGHAMTON, NY 13902  
(607) 777-3341 - FAX (607) 777-6643

**MEMORANDUM**

DATE: March 25, 2020

SUBJECT: **Addendum # 2**  
**Project #: 218122**  
**Title: West Gym Student Athlete Success Center**

**Bid Opening Date: April 6, 2020 at 2:30pm**

Please note the following addendum/changes in the bid proposal. All bids received will be in accordance with this addendum. All other specifications, terms and conditions remain the same.

1. Drawing A3.1.1 notes on the west side of corridor 152A "Corridor shall receive 5/8" GWB laminated to the block wall and vinyl base." Interior elevation 1/A12.1.2 indicates GWB laminated only between columns C-D. Please confirm that the only laminated board is shown on the interior elevation for corridor 152A.

Response: The note on the A3.1.1 drawing is pointing to the wrong wall; it should be indicating the east wall. The A12.1.2 drawing is correct. Only the wall area between the two columns is to receive the G.W.B lamination and base.

2. Spec section 012300 – alternates, alternate 1 mentions in the base bid description install of a decorative mineral board panel system as indicated on drawing A-5. Drawing A-5 was not provided, please provide.

Response: Any mention of an "A" drawing is in reference to an architectural sheet that has been renamed; hence, there are no "A" drawings. The A-5 drawing is now drawing A12.1.1. The mineral board panels are part of the base bid, as is the G.W.B. lamination on the block wall that does not receive the new panels. The alternate is to omit the G.W.B. while keeping the installation of the mineral boards.

3. Please confirm the decorative mineral board panel system is to be eliminated in alternate 1.

Response: NO. The mineral boards are part of the base bid and will be installed regardless of the omission of the G.W.B. Both Alternate #1 and Alternate #2 reference the elimination of the laminated gypsum board. NOTE: The elimination of the G.W.B. is to facilitate the installation of wood panels that will be provided by the furniture vendor. The wood panels may be eliminated due to cost constraints of the project. If this wood panel finish is desired, then the laminated gypsum board on the north and south walls of room 157 will not be needed.