CORNELL UNIVERSITY FACILITIES CONTRACTS 121 HUMPHREYS SERVICE BUILDING ITHACA, NEW YORK 14853-3701

ADDENDUM NO. 1

December 15, 2025

This Addendum contains changes to the requirements of the Contract Documents and Specifications. Such changes are to be incorporated into the Construction Documents and shall apply to the work with the same meaning and force as if they had been included in the original document. Wherever this Addendum modifies a portion of a paragraph of the specifications or a portion of any Drawing, the remainder of the Paragraph or Drawing shall remain in force.

NOTE: Provisions of all Contract Documents apply.

Note: Any specified materials, equipment, systems, etc., shall have "or equal to" added to the description if not already there. Contractors should note any substitutions in their bid submission.

Item 1. INSTRUCTIONS TO BIDDERS, INS-6, Item 15.c.

DELETE "...2:00PM on January 6, 2026",

REPLACE with "...2:00PM on January 13, 2026"

*The final RFI deadline is 12:00PM on January 2, 2026.

TECHNICAL SPECIFICATIONS

- Item 2. **ADD** Section 12 24 13 Roller Window Shades, attached.
- Item 3. Section 23 09 23 Building Automation Control System, Paragraph 1.2, A Description

DELETE Paragraph A in its entirety,

REPLACE with

A. Provide labor, materials, equipment and services as required for the complete installation designed in Contract Drawings. Extend existing Building Automation Control System (BACS), to perform the functions described in this Section. All new equipment shall be compatible with the existing system and provide feedback to the building central HVAC system controls for but not limited to supply temperature reset, static and differential pressure reset, heating and cooling requests. The existing building central HVAC system controls are Automated Logic Corporation. Provide wiring and conduit required to connect devices furnished as a part of, or accessory to, this automatic control system. Control wiring is defined as wiring up to and including 120 volts. Install wiring in accordance with requirements of "Electrical Wiring" in Section 230504, and the National Electrical Code. Provide all required devices for proper system operation, including special electrical switches, transformers, relays, pushbutton stations, etc.

Comstock Hall 5th Floor Lab and Support Space Renovations Addendum No. 1 December 15, 2025 Page 2

Item 4. Section 23 09 23, Paragraph 1.4, A – Acceptable Makes

DELETE Paragraph A in its entirety,

REPLACE with

A. The complete Building Management System is designed and based on that manufactured by Automated Logic Corporation. Acceptable Make: Automated Logic Corporation, Alerton (or equal.)

DRAWINGS

Item 5. DRAWING AD-101 – Fifth Floor Demolition Plan

DELETE in its entirety,

REPLACE with revised Drawing AD-101R, attached.

Item 6. DRAWING AD-111 – Fifth Floor Demolition RCP

DELETE in its entirety,

REPLACE with revised Drawing AD-111R, attached.

Item 7. DRAWING A-101 – Fifth Floor Plan

DELETE in its entirety,

REPLACE with revised Drawing A-101R, attached.

Item 8. DRAWING A-130 - Fifth Floor Reflected Ceiling Plan

DELETE in its entirety,

REPLACE with revised Drawing A-130R, attached.

Item 9. DRAWING A-421 – Interior Elevations

DELETE in its entirety,

REPLACE with revised Drawing A-421R, attached.

Item 10. Drawing MD-101 – Partial Fifth Floor Demolition Plan - Ductwork

DELETE in its entirety,

REPLACE with revised Drawing MD-101R, attached.

Comstock Hall 5th Floor Lab and Support Space Renovations Addendum No. 1 December 15, 2025 Page 3

Item 11. Drawing M-101- Partial Fifth Floor Plan - Ductwork

DELETE in its entirety.

REPLACE with revised Drawing M-101R attached.

Item 12. Drawing M-402 – Control Schematic and System Summaries

DELETE in its entirety.

REPLACE with revised Drawing M-402R attached.

Item 13. Drawing M-500 – Details - HVAC

DELETE in its entirety.

REPLACE with revised Drawing M-500R attached.

Item 14. Pre-bid Sign-in Sheet attached for Contractors' reference only.

Item 15. RFI Questions and Clarifications

See attached RFI Log Items (1-6)

Attachments: Section 12 24 13

Drawing AD-101R Drawing AD-111R Drawing A-101R Drawing A-130R Drawing A-421R Drawing MD-101R Drawing M-101R Drawing M-402R Drawing M-500R

Pre-bid Meeting Sign-in Sheet (for reference only)

RFI Log (Items 1 - 6)

****END OF ADDENDUM****

SECTION 12 24 13 - ROLLER WINDOW SHADES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Manually operated roller shades with single rollers.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - Include construction details, material descriptions, dimensions of individual components and profiles, features, finishes, and operating instructions for roller shades.
- B. Shop Drawings: Show fabrication and installation details for roller shades, including shadeband materials, their orientation to rollers, and their seam and batten locations.
- C. Samples for Initial Selection: For each type and color of shadeband material.
 - 1. Include Samples of accessories involving color selection.
- D. Samples for Verification: For each type of roller shade.
 - 1. Roller Shade: Full-size operating unit, not less than 16 inches wide by 36 inches long for each type of roller shade indicated.
 - 2. Installation Accessories: Full-size unit, not less than 10 inches long.
- E. Product Schedule: For roller shades. Use same designations indicated on Drawings.

1.3 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

1.4 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For roller shades to include in maintenance manuals.

1.5 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Roller Shades: Full-size units equal to 5 percent of quantity installed for each size, color, and shadeband material indicated, but no fewer than two units.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: Fabricator of products.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Deliver roller shades in factory packages, marked with manufacturer, product name, and location of installation using same designations indicated on Drawings.

1.8 FIELD CONDITIONS

- A. Environmental Limitations: Do not install roller shades until construction and finish work in spaces, including painting, is complete and dry and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.
- B. Field Measurements: Where roller shades are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication and indicate measurements on Shop Drawings. Allow clearances for operating hardware of operable glazed units through entire operating range. Notify Architect of installation conditions that vary from Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Source Limitations: Obtain roller shades from single source from single manufacturer.

2.2 MANUALLY OPERATED SHADES WITH SINGLE ROLLERS

- A. <u>Manufacturers:</u> Subject to compliance with requirements, provide products by one of the following:
 - 1. Draper, Inc.
 - 2. Lutron Electronics Co., Inc.
 - MechoShade Systems, LLC.
- B. Chain-and-Clutch Operating Mechanisms: With continuous-loop bead chain and clutch that stops shade movement when bead chain is released; permanently adjusted and lubricated.
 - 1. Bead Chains: Stainless steel .
 - a. Loop Length: Full length of roller shade.
 - b. Limit Stops: Provide upper and lower ball stops.
 - c. Chain-Retainer Type: Clip, jamb mount.
- C. Rollers: Corrosion-resistant steel or extruded-aluminum tubes of diameters and wall thicknesses required to accommodate operating mechanisms and weights and widths of shadebands indicated without deflection. Provide with permanently lubricated driveend assemblies and idle-end assemblies designed to facilitate removal of shadebands for service.
 - 1. Roller Drive-End Location: Right side of interior face of shade.
 - 2. Direction of Shadeband Roll: Regular, from back (exterior face) of roller.
 - 3. Shadeband-to-Roller Attachment: Manufacturer's standard method.

D. Mounting Hardware: Brackets or endcaps, corrosion resistant and compatible with roller assembly, operating mechanism, installation accessories, and mounting location and conditions indicated.

E. Shadebands:

- 1. Shadeband Material: Light-filtering fabric.
- 2. Shadeband Bottom (Hem) Bar: Steel or extruded aluminum.
 - a. Type: Exposed with endcaps and integral light seal at bottom where it meets the sill.
 - b. Color and Finish: As selected by Architect from manufacturer's full range.

F. Installation Accessories:

- 1. Front Fascia: Aluminum extrusion that conceals front and underside of roller and operating mechanism and attaches to roller endcaps without exposed fasteners.
 - a. Shape: L-shaped.
 - b. Height: Manufacturer's standard height required to conceal roller and shadeband assembly when shade is fully open, but not less than 4 inches.
- 2. Endcap Covers: To cover exposed endcaps.
- 3. Installation Accessories Color and Finish: As selected from manufacturer's full range.

2.3 SHADEBAND MATERIALS

- A. Shadeband Material Flame-Resistance Rating: Comply with NFPA 701. Testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
- B. Light-Filtering Fabric: Woven fabric, stain and fade resistant.
 - 1. Source: Roller shade manufacturer.
 - 2. Type: Woven polyester and PVC-coated polyester.
 - Weave: Mesh.
 - 4. Openness Factor: 3 percent.
 - 5. Color: As indicated on Drawings.

2.4 ROLLER SHADE FABRICATION

- A. Product Safety Standard: Fabricate roller shades to comply with WCMA A 100.1, including requirements for flexible, chain-loop devices; lead content of components; and warning labels.
- B. Unit Sizes: Fabricate units in sizes to fill window and other openings as follows, measured at 74 deg F:
 - 1. Between (Inside) Jamb Installation: Width equal to jamb-to-jamb dimension of opening in which shade is installed less 1/4 inch per side or 1/2-inch total, plus or minus 1/8 inch. Length equal to head-to-sill or -floor dimension of opening in which shade is installed less 1/4 inch, plus or minus 1/8 inch.
 - 2. Outside of Jamb Installation: Width and length as indicated, with terminations between shades of end-to-end installations at centerlines of mullion or other defined vertical separations between openings.

- C. Shadeband Fabrication: Fabricate shadebands without battens or seams to extent possible, except as follows:
 - 1. Vertical Shades: Where width-to-length ratio of shadeband is equal to or greater than 1:4, provide battens and seams at uniform spacings along shadeband length to ensure shadeband tracking and alignment through its full range of movement without distortion of the material.
 - 2. Railroaded Materials: Railroad material where material roll width is less than the required width of shadeband and where indicated. Provide battens and seams as required by railroaded material to produce shadebands with full roll-width panel(s) plus, if required, one partial roll-width panel located at top of shadeband.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, operational clearances, locations of connections to building electrical system, and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 ROLLER SHADE INSTALLATION

- A. Install roller shades level, plumb, and aligned with adjacent units according to manufacturer's written instructions.
- B. Roller Shade Locations: As indicated on Drawings.

3.3 ADJUSTING

A. Adjust and balance roller shades to operate smoothly, easily, safely, and free from binding or malfunction throughout entire operational range.

3.4 CLEANING AND PROTECTION

- A. Clean roller shade surfaces, after installation, according to manufacturer's written instructions.
- B. Provide final protection and maintain conditions, in a manner acceptable to manufacturer and Installer, that ensure that roller shades are without damage or deterioration at time of Substantial Completion.
- C. Replace damaged roller shades that cannot be repaired, in a manner approved by Architect, before time of Substantial Completion.

END OF SECTION 12 24 13

GENERAL DEMOLITION NOTES

1. DOCUMENTATION OF EXISTING CONDITIONS IS DERIVED FROM EXISTING SURVEYS, DRAWINGS AND LIMITED FIELD INSPECTION. PRIOR TO THE SUBMISSION OF BIDS, CONTRACTORS SHALL WALK THE SITE AND SATISFY THEMSELVES TO EXISTING VISUAL CONDITIONS. THE ARCHITECT SHALL BE CONSULTED WHEN ANY QUESTION ARISES RELATIVE TO MATERIALS AND CONDITIONS NOT SPECIFICALLY SHOWN

2. ALL EXISTING WORK (CEILING, FLOORS, WALLS, FINISHES, ETC.) DISTURBED BY NEW CONSTRUCTION SHALL BE PATCHED AND REFINISHED. PATCHING AND FINISH WORK IS THE REPAIR WORK REQUIRED TO RESTORE SURFACES TO THE ORIGINAL CONDITION AND/ OR MATCHING THE ADJACENT SURFACES. MISCELLANEOUS FINISH REQUIREMENTS TO WALL, FLOOR AND CEILING IN AREAS AFFECTED BY DEMOLITION HAVE NOT BEEN TOTALLY INCORPORATED INTO THE ROOM FINISH SCHEDULE. REFER TO THE DEMOLITION, FLOOR AND REFLECTED CEILING PLANS FOR ADDITIONAL CUTTING, PATCHING AND REFINISHING WORK SCOPE.

3. ALL EXISTING FIRE-RESISTANT CONSTRUCTION MUST BE MAINTAINED OR MADE TO COMPLY WITH THE REQUIREMENTS AS ESTABLISHED BY THIS CONTRACT. SEE THE CODE COMPLIANCE PLANS FOR THE FIRE RESISTANT RATINGS OF EXISTING AND NEW CONSTRUCTION.

4. CARE SHALL BE TAKEN TO LIMIT IMPACT OF CONSTRUCTION ON THE SURROUNDING OCCUPANTS AND OPERATIONS DURING THE PROJECT. SAFE LEGAL PASSAGES SHALL BE PROVIDED FOR ALL BUILDING OCCUPANTS DURING ALL THE PHASES OF THIS PROJECT. THE CONTRACTOR SHALL COORDINATE PATHWAYS FOR CONSTRUCTION ACTIVITY AND SCHEDULE LOUD WORK WITH OWNER PRIOR TO COMMENCING CONSTRUCTION.

5. ALL CONTRACTORS ARE RESPONSIBLE FOR CUTTING AND PATCHING REQUIRED TO COMPLETE THEIR WORK. FOR NEW OPENINGS IN EXISTING MASONRY WALLS, UNLESS SPECIFICALLY INDICATED OTHERWISE, THE TRADE REQUIRING THE OPENING SHALL PROVIDE THE DEMOLITION, LINTEL INSTALLATION AND RECONSTRUCTION.

6. CONTRACTORS ARE TO PROVIDE ADEQUATE SUPPORT FOR WALLS, LOAD-BEARING WALLS, AND PARTITIONS DURING DEMOLITION AND CONSTRUCTION.

7. WHEN EXISTING CONSTRUCTION WHICH IS TO REMAIN IS DAMAGED DURING THE COURSE OF CONSTRUCTION AS A RESULT OF CONTRACTOR'S WORK, IT SHALL BE REPAIRED AND/OR REPLACED WITH SIMILAR OR LIKE MATERIALS, SUBJECT TO ARCHITECT'S APPROVAL AND WITHOUT COMPENSATION.

8. ALL EXISTING FURNITURE AND EQUIPMENT TO BE REMOVED BY OWNER PRIOR TO START OF DEMOLITION. ALL EXISTING CASEWORK OR EQUIPMENT TO BE REMOVED AND INSTALLED, SHALL BE STORED BY CONTRACTOR TO FACILITATE FLOORING IMPROVEMENTS.

5TH FLOOR DEMOLITION KEY NOTES

SHOWN AS: X

260 E Main St Suite 4000 Rochester, NY 14604 585 232 8300 | rochester@swbr.com

> SWBR NYS Certificate of Authorization #: 235221

Issue Date: 12/12/25

Registration Expires: 11/30/27

DESCRIPTION CLEAN AND PREP EPOXY FLOORING AND INTEGRAL BASE TO RECEIVE NEW EPOXY FINISHES. GRIND DOWN HIGH SPOTS AND PATCH LOW SPOTS WITH EPOXY MORTAR TO PROVIDE CONSISTENT LEVEL SURFACE. SOUND AND REMOVE ANY UNBONDED AREAS. MECHANICALLY PREPARE LEVELED SURFACE WITH DUSTLESS GRINDING OR SANDING. PROVIDE PRIMER AT MANUFACTURER'S RECOMMENDATION.

MATCHEDIAREAUNDICATES/REMOVAL OF CONCRETE PAD. PREPTIME SURFACE TO RECEIVE SCHEDULED FLOORING AND WALL BASE. REMOVE CHAMBER IN ITS ENTIRETY, INCLUDING ALL ATTACHED DUCTWORK, PIPING, AND

CONDUIT. REFER TO MEP DRAWINGS FOR COMPLETE SCOPE OF SYSTEMS DISCONNECTION. REMOVE CHALK/WHITEBOARD, PATCH WALL SURFACE AT REMOVAL.

FURNITURE/EQUIPMENT TO BE REMOVED AND STORED BY OWNER, TYP.

LAB TABLES AND BENCH TO REMAIN.

REMOVE WALL SHELF AND STANDARDS, PATCH WALL AT REMOVAL OF ANCHORS. REMOVE VCT FLOORING AND RESILIENT WALL BASE. PREP CONCRETE SUBSTRATE TO RECEIVE

REMOVE COAT HOOKS.

REMOVE SINK AND BASE. CAP PLUMBING FOR SALVAGED SINK INSTALLATION. SEE PLUMBING DWGS. PATCH WALLS AND FLOOR AT REMOVAL OF BASE CABINET. REMOVE LAB BENCH IN ITS ENTIRETY INCLUDING SINK AND BASE. CAP PLUMBING FOR NEW SINK INSTALLATION. SEE PLUMBING DWGS. PATCH WALLS AND FLOOR AT REMOVAL OF BENCH

REMOVE UTILITY CHASE. REMOVE LAB BENCH, CASEWORK, AND UPPER SHELVING ASSEMBLY WHERE PRESENT IN ITS ENTIRETY, INCLUDING ALL SERVICE CONNECTIONS.

REMOVE & SALVAGE STAINLESS SINK TO BE RELOCATED TO ROOM 5132. CAP PLUMBING PIPING, SEE PLUMBING DWGS. PATCH WALLS AT REMOVAL OF SINK. REMOVE LIGHT FIXTURE, SEE ELEC. DWGS.

REMOVE SUSPENDED CEILING GRID AND PANELS, INCLUDING ALL LIGHTING, AIR TERMINALS, AND OTHER DEVICES LOCATED IN THE CEILING SYSTEM. SEE MEP DWGS FOR COMPLETE SCOPE OF

REMOVE & SALVAGE SUSPENDED CEILING GRID AND PANELS. SALVAGE CEILING MOUNT LIGHT FIXTURES FOR REINSTALLATION. SEE MEP DWGS FOR COMPLETE SCOPE OF REMOVALS. FUME HOOD TO REMAIN. PROTECTIVE MEASURES SHALL BE TAKEN DURING CONSTRUCTION. FLAMMABLE CABINET TO REMAIN. PROTECTIVE MEASURES SHALL BE TAKEN DURING

CONSTRUCTION. SALVAGE FURNITURE/EQUIPMENT TO BE STORED AND REINSTALLED BY OWNER, TYP

AT DOORS LOCATED IN CORRIDOR WALL THAT IS NO LONGER CONSIDERED RATED, REMOVE ANY TAGS INDICATING A FIRE RATING AND PROVIDE TAGS ON HINGE SIDE OF DOOR AND FRAME INDICATING THAT OPENING HAS BEEN DECOMMISSIONED. BOD LABEL: REMEDI8

LBL-FDS-DECOMLBL. AT CORRIDOR WALL THAT IS NO LONGER CONSIDERED RATED, REMOVE ANY TAGS OR STENCILS INDICATING THAT THE PARTITION AND ANY FIRESTOPPED THROUGH PENETRATIONS ARE RATED. REMOVE ONE (1) FIRE DAMPER WITHIN THE RENOVATION AREA. PROVIDE STENCILS AT 8' - 0" AFF

AND SPACED AT 48" OC MAX ALONG LENGTH OF CORRIDOR WALL AT WORK AREA INDICATING THAT PARTITION IS DECOMMISSIONED. SEE STENCIL DETAIL 2/AD-101R. REMOVE DECOMMISSIONED FUME HOOD COORDINATE WITH OWNER'S REPRESENTATIVE BEFER

TO MECHANICAL AND PLUMBING DRAWINGS FOR ADDITIONAL INFORMATION. REMOVE DOOR, ERAME AND HARDWARE.

EXTENT OF REMOVALS AT 4TH FLOOR SPLINE CEILING TO FACILITATE PLUMBING INSTALLATION. SEE 2/A-130. APPROXIMATELY 120 SF. REMOVE AND SALVAGE EXISTING LIGHTING, AIR TERMINALS,

AND OTHER CEILING-MOUNTED FIXTURES WITHIN AREA REQUIRED FOR PLUMBING INSTALLATION. -2X REMOVE AND SALVAGE FIRE EXTINGUISHER FOR REINSTALLATION. REMOVE EXISTING WALL! REMOVE GYP BOARD PARTITION IN FRONT OF EXISTING WINDOW. CLEAN HEAD AND SILL AT

PLEASE NOTE: MOTALL KEYNOTES USED IN EACH VIEW.

WALL STENCIL (BLACK) LOCATED AT 8'-0" AFF IN AREA OF DECOMMISSIONED PARTITION, LETTERING APPROX. 1" IN HEIGHT. PROVIDE GRAPHICS INDICATING EXTENT OF DECOMMISIONED PARTITON, TO BOUNDARIES OUTLINED ON FLOOR PLANS.

DECOMMISSIONED PARTITION WALL ASSEMBLY AND PENETRATIONS — NOT CONSIDERED RATED IN THIS AREA

<u>\ DECOMMISSIONED PARTITON STENCIL</u>

person, firm, or corporation for any purpose whatsoever except with the specific written permission of SWBR. All rights reserved. © Revisions

Project Manager: MJP

These documents and all the ideas, arrangements, designs and plans indicated thereon or presented thereby are owned by and remain the property of SWBR and no part thereof shall be utilized by any

1 12/17/2025 Addendum #1

Drawn By: Checked By:

COMSTOCK HALL 5TH FLOOR

LAB AND SUPPORT SPACE 129 Garden Ave Ithaca, NY 14853 SWBR Project Number 25044.00

Cornell University Ithaca, NY 14853

AD-101R FIFTH FLOOR **DEMOLITION PLAN**

11/7/2025 100% Construction Documents

1 PARTIAL FIFTH FLOOR DEMOLITION PLAN

GENERAL DEMOLITION NOTES

- 1. DOCUMENTATION OF EXISTING CONDITIONS IS DERIVED FROM EXISTING SURVEYS, DRAWINGS AND LIMITED FIELD INSPECTION. PRIOR TO THE SUBMISSION OF BIDS, CONTRACTORS SHALL WALK THE SITE AND SATISFY THEMSELVES TO EXISTING VISUAL CONDITIONS. THE ARCHITECT SHALL BE CONSULTED WHEN ANY QUESTION ARISES RELATIVE TO MATERIALS AND CONDITIONS NOT SPECIFICALLY SHOWN
- 2. ALL EXISTING WORK (CEILING, FLOORS, WALLS, FINISHES, ETC.) DISTURBED BY NEW CONSTRUCTION SHALL BE PATCHED AND REFINISHED. PATCHING AND FINISH WORK IS THE REPAIR WORK REQUIRED TO RESTORE SURFACES TO THE ORIGINAL CONDITION AND/ OR MATCHING THE ADJACENT SURFACES. MISCELLANEOUS FINISH REQUIREMENTS TO WALL. FLOOR AND CEILING IN AREAS AFFECTED BY DEMOLITION HAVE NOT BEEN TOTALLY INCORPORATED INTO THE ROOM FINISH SCHEDULE. REFER TO THE DEMOLITION, FLOOR AND REFLECTED CEILING PLANS FOR ADDITIONAL CUTTING, PATCHING AND REFINISHING WORK SCOPE.
- 3. ALL EXISTING FIRE-RESISTANT CONSTRUCTION MUST BE MAINTAINED OR MADE TO COMPLY WITH THE REQUIREMENTS AS ESTABLISHED BY THIS CONTRACT. SEE THE CODE COMPLIANCE PLANS FOR THE FIRE RESISTANT RATINGS OF EXISTING AND NEW CONSTRUCTION.
- 4. CARE SHALL BE TAKEN TO LIMIT IMPACT OF CONSTRUCTION ON THE SURROUNDING OCCUPANTS AND OPERATIONS DURING THE PROJECT. SAFE LEGAL PASSAGES SHALL BE PROVIDED FOR ALL BUILDING OCCUPANTS DURING ALL THE PHASES OF THIS PROJECT. THE CONTRACTOR SHALL COORDINATE PATHWAYS FOR CONSTRUCTION ACTIVITY AND SCHEDULE LOUD WORK WITH OWNER PRIOR TO COMMENCING CONSTRUCTION.
- 5. ALL CONTRACTORS ARE RESPONSIBLE FOR CUTTING AND PATCHING REQUIRED TO COMPLETE THEIR WORK. FOR NEW OPENINGS IN EXISTING MASONRY WALLS, UNLESS SPECIFICALLY INDICATED OTHERWISE, THE TRADE REQUIRING THE OPENING SHALL PROVIDE THE DEMOLITION, LINTEL INSTALLATION AND RECONSTRUCTION.
- 6. CONTRACTORS ARE TO PROVIDE ADEQUATE SUPPORT FOR WALLS, LOAD-BEARING WALLS, AND PARTITIONS DURING DEMOLITION AND CONSTRUCTION.
- 7. WHEN EXISTING CONSTRUCTION WHICH IS TO REMAIN IS DAMAGED DURING THE COURSE OF CONSTRUCTION AS A RESULT OF CONTRACTOR'S WORK, IT SHALL BE REPAIRED AND/OR REPLACED WITH SIMILAR OR LIKE MATERIALS, SUBJECT TO ARCHITECT'S APPROVAL AND WITHOUT COMPENSATION.
- 8. ALL EXISTING FURNITURE AND EQUIPMENT TO BE REMOVED BY OWNER PRIOR TO START OF DEMOLITION. ALL EXISTING CASEWORK OR EQUIPMENT TO BE REMOVED AND INSTALLED, SHALL BE STORED BY CONTRACTOR TO FACILITATE FLOORING IMPROVEMENTS.

5TH FLOOR DEMOLITION KEY NOTES

SHOWN AS: X 1 CLEAN AND PREP EPOXY FLOORING AND INTEGRAL BASE TO RECEIVE NEW EPOXY FINISHES. GRIND DOWN HIGH SPOTS AND PATCH LOW SPOTS WITH EPOXY MORTAR TO PROVIDE CONSISTENT LEVEL SURFACE. SOUND AND REMOVE ANY UNBONDED AREAS. MECHANICALLY PREPARE LEVELED SURFACE WITH DUSTLESS GRINDING OR SANDING. PROVIDE PRIMER AT

MANUFACTURER'S RECOMMENDATION. SCHEDULED FLOORING AND WALL BASE.

- TAGS INDICATING A FIRE RATING AND PROVIDE TAGS ON HINGE SIDE OF DOOR AND FRAME INDICATING THAT OPENING HAS BEEN DECOMMISSIONED. BOD LABEL: REMEDI8 LBL-FDS-DECOMLBL.
- AT CORRIDOR WALL THAT IS NO LONGER CONSIDERED RATED. REMOVE ANY TAGS OR STENCILS INDICATING THAT THE PARTITION AND ANY FIRESTOPPED THROUGH PENETRATIONS ARE RATED. REMOVE ONE (1) FIRE DAMPER WITHIN THE RENOVATION AREA. PROVIDE STENCILS AT 8' - 0" AFF AND SPACED AT 48" OC MAX ALONG LENGTH OF CORRIDOR WALL AT WORK AREA INDICATING THAT PARTITION IS DECOMMISSIONED. SEE STENCIL DETAIL 2/AD-101R.
- TO MECHANICAL AND PLUMBING DRAWINGS FOR ADDITIONAL INFORMATION. EXTENT OF REMOVALS AT 4TH FLOOR SPLINE CEILING TO FACILITATE PLUMBING INSTALLATION.

PARTIAL FOURTH FLOOR CEILING DEMOLITION PLAN

1/8" = 1'-0"

Revisions 1 12/17/2025 Addendum #1 - GENERAL ROUTING FOR PLUMBING WORK. OPEN CEILING IN THIS AREA, COORDINATE PLUMBING WORK WITH EXISTING UTILITIES. SEE PLUMBING DWGS.

> LAB AND SUPPORT SPACE 129 Garden Ave Ithaca, NY 14853 SWBR Project Number 25044.00

COMSTOCK HALL 5TH FLOOR

Checked By:

Project Manager: MJP

These documents and all the ideas, arrangements, designs and plans indicated thereon or presented thereby are owned by and remain the property of SWBR and no part thereof shall be utilized by any person, firm, or corporation for any purpose whatsoever except with the specific written permission of SWBR. All rights reserved. ©

260 E Main St Suite 4000 Rochester, NY 14604

585 232 8300 | rochester@swbr.com SWBR NYS Certificate of

Authorization #: 235221


Issue Date: 12/12/25

Registration Expires: 11/30/27

Cornell University Ithaca, NY 14853

AD-111R FIFTH FLOOR DEMOLITION RCP

11/7/2025 100% Construction Documents




1) PARTIAL FIFTH FLOOR CEILING DEMOLITION PLAN

1/4" = 1'-0"

5130





PARTIAL FIFTH FLOOR PLAN

1/4" = 1'-0"

GENERAL NEW WORK NOTES:

1. ALL FLOORS, WALLS, CEILINGS, AND OTHER SURFACES THAT ARE TO REMAIN ARE TO BE PATCHED, REPAIRED, AND REFINISHED PRIOR TO FINISH INSTALLATION. ALL SURFACES ARE TO BE RESTORED TO THEIR ORIGINAL CONDITION AND/OR MATCH THE ADJACENT SURFACES. 2. NEW ADA FUME HOOD ("FH-1)").

	5TH FLOOR PLAN KEY NOTES	
		SHOWN AS: (
NO.	DESCRIPTION	·
1	LAB EQUIPMENT/FURNITURE - N.I.C. SEE A-800 EQUIPMENT PLAN FOR MORE INFORM	ATION.
2	REPLACE EXISTING FUME HOOD WITH 60" ADA FUME HOOD ON AN ADJUSTABLE BAS	E.
3	PROVIDE ACCESSIBLE, STEPPED BOTTOM DROP-IN EPOXY RESIN LAB SINK, SK-A 25" PURE WATER FAUCET AND EMERGENCY EYE WASH. SEE PLUMBING DRAWINGS.	X15"X4.75". PROVIDE
4	PROVIDE GYP BOARD AND METAL STUD PARTITION TO MATCH EXISTING ADJACENT V GYP BD TO MATCH ADJACENT WALL FINISH. PROVIDE SCHEDULED WALL BASE.	WALL. PREP AND PAII
5	PROVIDE BENCH-MOUNT GAS CYLINDER RESTRAINT (2). BASIS-OF-DESIGN: USA SAFI	ETY GB250FS.
6	PROVIDE WALL-MOUNT GAS CYLINDER RESTRAINTS, NUMBER OF CYLINDERS AS IND BASIS-OF-DESIGN: USA SAFETY GB200FS AND GB300FS. PROVIDE A CHEMICAL SEGR INDICATING APPROPRIATE STORAGE METHOD.	ICATED.
7	PROVIDE EPOXY FLOORING AND INTEGRAL BASE, REFER TO FINISH PLANS.	
8	PREP AND PAINT WALLS, REFER TO FINISH SCHEDULE.	
9	PROVIDE FIXED LAB FURNITURE INCLUDING COUNTERTOP, BACKSPLASH, SIDESPLAS BASE CABINETS, AND UPPER SHELVING.	SH, PAINTED STEEL
10	EXISTING LAB FURNITURE/CASEWORK TO REMAIN. PROTECT DURING DEMOLITION A	ND CONSTRUCTION.
11	MANUAL RETRACTABLE INSECT CURTAIN. PROVIDE CEILING GRID-MOUNTED ALUMIN CURVING CORNER, EXTENDING TIGHT TO ADJACENT WALLS. PROVIDE NYLON ROLLE FOR SUSPENDING CURTAIN. PROVIDE MIN. 12" VALANCE ATTACHED TO TRACK AND TOURTAIN TO BE AFFIXED TO SIDE WALLS WITH SCREW ANCHORS SO THAT THERE AFFIXED TO SIDE WALLS WITH SCREW ANCHORS SO THAT THERE AFFIXED OF CURTAIN AND WALL SURFACE. PROVIDE MAGNETIC OR ZIPPER TRACK THE CURTAIN, AND GASKET AND BOTTOM POCKET WITH CHAIN OR ROPE WEIGHT. BASIS-OF-DESIGN FOR INSECT CURTAIN MATERIAL: PHIFER SHEERWEAVE 2360, .011. BASIS-OF-DESIGN FOR CURTAIN TRACK: AKON CURTAINS	ER HOOK TROLLEYS FIGHT TO CEILING. RE NO GAPS BETWEE IN THE CENTER OF
12	54" X 24" CANTILEVERED EPOXY RESIN LAB WORKBENCH ON FULL-HEIGHT 12" ISLANI PANELS. BASIS-OF-DESIGN: MOTT SIGMA FLEX.	D CORE WITH FILLER
13	54" X 24" CANTILEVERED EPOXY RESIN LAB WORKBENCH ON LOWER-HEIGHT 12" ISLAFILLER PANELS. BASIS-OF-DESIGN: MOTT SIGMA FLEX.	
14	60" x 28" FREESTANDING METAL ADAPTABLE LAB TABLE SYSTEM WITH 60" X 30" EPOX COUNTERTOP. BASIS-OF-DESIGN: MOTT ALTUS.	
15	54" x 28" FREESTANDING METAL ADAPTABLE LAB TABLE SYSTEM WITH 54" X 30" EPOX COUNTERTOP. BASIS-OF-DESIGN: MOTT ALTUS.	
16	72" x 28" FREESTANDING METAL ADAPTABLE LAB TABLE SYSTEM WITH 72" X 30" EPOX COUNTERTOP. BASIS-OF-DESIGN: MOTT ALTUS.	XY RESIN
17	66" x 28" FREESTANDING METAL ADAPTABLE LAB TABLE SYSTEM WITH 66" X 30" EPOX COUNTERTOP. BASIS-OF-DESIGN: MOTT ALTUS.	XY RESIN
19	PROVIDE 36"W X 14"D X 84"H TALL CABINETS WITH HINGED FRAMED GLASS DOOR UN BASIS-OF-DESIGN: MOTT STEEL FLOOR CABINETS - 6410030	NITS.
20	48" x 28" FREESTANDING METAL ADAPTABLE LAB TABLE SYSTEM WITH 72" X 30" EPOX COUNTERTOP. BASIS-OF-DESIGN: MOTT ALTUS.	XY RESIN
21	42" x 28" FREESTANDING METAL ADAPTABLE LAB TABLE SYSTEM WITH 72" X 30" EPOX COUNTERTOP. BASIS-OF-DESIGN: MOTT ALTUS.	XY RESIN
22	WALL-MOUNTED FIRE EXTINGUISHER, SEE DETAIL 2/G-001.	
23	PROVIDE 30"W X 14"D X 84"H TALL CABINETS WITH HINGED FRAMED GLASS DOOR UN BASIS-OF-DESIGN: MOTT STEEL FLOOR CABINETS - 6410030	NTS.
24	PROVIDE FIRESTOPPED THROUGH PENETRATIONS FOR NEW UTILITIES. AT EXISTING SHAFTWALL, PROVIDE FIRESTOPPING AT ALL NON-CONFORMING PENETRATIONS, AN TO ALL VOIDS IN THE SHAFTWALL. SEE PENETRATION SCHEDULE ON G-002 FOR LIST PENETRATION TYPES, MATERIALS, AND RECOMMENDED U.L. SYSTEMS. COORDINATE ELEVATIONS, AND PENETRATION SIZING WITH MEP/FP DRAWINGS.	ND ADD FIRESTOPPIN TING OF APPLICABLE
25	PROVIDE HOLLOW METAL CASED OPENING AT DOOR REMOVAL, PAINT.	
26	PROVIDE THROUGH PENETRATIONS FOR NEW SINK/EQUIPMENT. SEE PENETRATION FOR LISTING OF APPLICABLE PENETRATION TYPES, MATERIALS, AND RECOMMENDE COORDINATE ALL LOCATIONS, ELEVATIONS, AND PENETRATION SIZING WITH PLUMB	D U.L. SYSTEMS.
27	EXTENT OF PLUMBING WORK ON THE 4TH FLOOR. SEE 2/A-130. PROVIDE GYP BOARD SALVAGED BACKUP SUSPENSION SYSTEM. PROVIDE FINISHED CEILING CONSISTENT ADJACENT. REINSTALL LIGHTING, AIR TERMINALS, AND OTHER FIXTURES THAT WERE FACILITATE PLUMBING INSTALLATION.	WITH EXISTING
28	SALVAGED SINK WITH NEW FIXTURES. SEE PLUMBING DRAWINGS.	
~29~	LAB CASEWORK SERVICE CHASE, FULL WIDTH OF SERVICE CORE AND 12' DEER	~~~~
30	PROVIDE ADDITIONAL FRAMING/BLOCKING FOR GYP BOARD RETURN JAMBS AT OPE MATCH EXISTING PARTITION. PROVIDE TEAR-AWAY BEAD AT GLASS, AND CAULK FUL	NING AND FINISH TO

OTHER ADJACENT MATERIALS. FIFTH FLOOR - FINISH SCHEDULE

ROOM		FLOOR	BASE	WALL	
NUMBER	ROOM NAME	FINISH	FINISH	FINISH	CEILING FINISH
5119	SHARED EQUIPMENT	RES-1	SSF-1	PT-1	ACT-1
5121	RESEARCH LAB	ETR	ETR	PT-1	ETR/SALVAGED
5121A	LAB SUPPORT	ETR	ETR	PT-1	ETR/SALVAGED
5123	RESEARCH LAB	RES-1	SSF-1	PT-1	ACT-1
5123A	LAB SUPPORT	RES-1	SSF-1	PT-1	ACT-1
5123B	LAB SUPPORT	RES-1	SSF-1	PT-1	ACT-1
5123C	RESEARCH LAB	RES-1	SSF-1	PT-1	ACT-1
5132	RESEARCH LAB	RES-1	SSF-1	PT-1	ETR/SALVAGED
·		·	·	·	· · · · · · · · · · · · · · · · · · ·

INTERIOR FINISHES & MATERIALS LIST (BY SPEC SECTION)

SOLID SURFACE FABRICATIONS WILSONART, COLOR: BLACK ONYX MIRAGE 9092MG, 1/2" THICK, 4" HIGH BASE, SEALED TO FLOOR AND WALL WITH CORA 898 SILICONE SEALANT, INCLUDE JOINT SEALANT AT ALL HORIZONTAL AND VERTICAL FLOOR, WALL, AND BASE CABINET SURFACES.

<u>SECTION 09 51 13 - ACOUSTICAL PANEL CEILINGS</u> ACOUSTICAL CEILING TILES (ACT)

ACT-1 ARMSTRONG CLEANROOM FL

<u>SECTION 09 67 23 – RESINOUS FLOORING</u> EPOXY FLOORING WITH INTEGRAL BASE **RES-1** SHERWIN WILLIAMS, RESUFLOR TOPCOAT SL123 SELF-LEVELING SLURRY,

GRIT LEVEL: MATCH EXISTING LABS, COLOR: STEEL GRAY #54 <u>SECTION 09 91 00 - INTERIOR PAINTING</u> PAINT (PT)

SHERWIN WILLIAMS OR BENJAMIN MOORE, FOR GYP BOARD AND MASONRY WALLS, COLOR: PT-1 MATCH EXISTING LABS SHERWIN WILLIAMS OR BENJAMIN MOORE, FOR HM DOORS AND FRAMES, COLOR: MATCH

EXISTING LABS

MANUFACTURER'S STANDARD RANGE.

<u>SECTION 12 24 13 - ROLLER WINDOW SHADES</u> WINDOW TREATMENTS (WT) WT-1 DRAPER INC. STYLE: 3G MERMET COMPANY M-SCREEN #008503 - FLEX SHADE MESH SHADE FASCIA, MANUAL CLUTCH CONTROL, 3% OPENNESS, SHADE AND HARDWARE COLORS: AS SELECTED FROM Project Manager: MJP


These documents and all the ideas, arrangements, designs and plans indicated thereon or presented thereby are owned by and remain the property of SWBR and no part thereof shall be utilized by any person, firm, or corporation for any purpose whatsoever except with the specific written permission of SWBR. All rights reserved. ©

Revisions 1 12/17/2025 Addendum #1

COMSTOCK HALL 5TH FLOOR LAB AND SUPPORT SPACE 129 Garden Ave Ithaca, NY 14853 SWBR Project Number 25044.00

Cornell University Ithaca, NY 14853

A-101R FIFTH FLOOR PLAN



260 E Main St Suite 4000 Rochester, NY 14604
585 232 8300 | rochester@swbr.com

SWBR NYS Certificate of
Authorization #: 235221

ON D. FERNAND. FERNAND.

Issue Date: 12/12/25
Registration Expires: 11/30/27

RCP LEGEND

X/- CEILING TYPE

PT-X-PAINT COLOR

2' X 2' SUSPENDED ACOUSTICAL CEILING

TO E SERIES DWGS

TO M-SERIES DWGS

2' X 4' LIGHT FIXTURE - REFER

SUPPLY DIFFUSER - REFER

Drawn By: SM

Checked By: MJP

Project Manager: MJP

These documents and all the ideas, arrangements, designs and plans indicated thereon or presented thereby are owned by and remain the property of SWBR and no part thereof shall be utilized by any person, firm, or corporation for any purpose whatsoever except with the specific written permission of SWBR. All rights reserved. ©

Revisions

1 12/17/2025 Addendum #1

1 12/1//2025 Addendum

COMSTOCK HALL 5TH FLOOR LAB AND SUPPORT SPACE RENOVATIONS 129 Garden Ave Ithaca, NY 14853

SWBR Project Number 25044.00

Cornell University Ithaca, NY 14853

A-130R
FIFTH FLOOR
REFLECTED
CEILING PLAN



260 E Main St Suite 4000 Rochester, NY 14604 585 232 8300 | rochester@swbr.com SWBR NYS Certificate of Authorization #: 235221 Issue Date: 12/12/25 Registration Expires: 11/30/27

LAB CASEWORK LEGEND

BC BASE CABINET


Checked By: Project Manager: MJP These documents and all the ideas, arrangements designs and plans indicated thereon or presented thereby are owned by and remain the property of SWBR and no part thereof shall be utilized by any person, firm, or corporation for any purpose whatsoever except with the specific written permission of SWBR. All rights reserved. © Revisions 1 12/17/2025 Addendum #1 **COMSTOCK HALL 5TH FLOOR** LAB AND SUPPORT SPACE 129 Garden Ave Ithaca, NY 14853

SWBR Project Number 25044.00 **Cornell University**

Ithaca, NY 14853

A-421R

INTERIOR **ELEVATIONS**



X DEMOLITION NOTES:

- 1 DISCONNECT AND REMOVE THE EXISTING ALTERTON CONTROLS FOR THE EXISTING TO REMAIN SUPPLY AIR TERMINAL UNIT.
- 2 DISCONNECT AND REMOVE DUCTWORK AND ALL ASSOCIATED ACCESSORIES BACK TO MAIN /INDICATED POINT. CAP AND SEAL AIR TIGHT.
- 3 DISCONNECT AND REMOVE DUCTWORK AND ALL ASSOCIATED ACCESSORIES BACK TO MAIN /INDICATED POINT. PREP FOR CONNECTION TO NEW.
- 4 DISCONNECT AND REMOVE EXISTING AIR TERMINAL UNIT AND ALL ASSOCIATED DUCTWORK AND CONTROLS.
- 5 DISCONNECT AND REMOVE DUCTWORK AS REQUIRED TO INSTALL NEW AIR VALVE.
 6 DISCONNECT AND REMOVE EXISTING DIFFUSER AND ASSOCIATED BRANCH DUCTWORK. REMOVE
- DUCTWORK BACK TO THE MAIN AND CAP AND SEAL AIR TIGHT.
- 7 DISCONNECT AND REMOVE DUCTWORK BACK TO FUME HOOD CONNECTION.
 8 DISCONNECT AND REMOVE EXISTING FIRE DAMPER. CORRIDOR WALL IS NO LONGER RATED
- CONSTRUCTION

 9 DISCONNECT AND REMOVE EXISTING FIRE DAMPER. FUME HOOD EXHAUST DUCTWORK SHALL NO INCLUDE FIRE DAMPERS PER CURRENT CODE.

10 DECOMMISSION AND TAG FIRE DAMPER OUT OF SERVICE. REMOVE FUSIBLE LINK AND EXISTING SHUTTER.)



387 East Main Street Rochester NY 14604 585 232 8300 | rochester@swbr.com SWBR NYS Certificate of Authorization #: 235221



is now Salas O'Brien
Consulting and Engineering
Group of New York, Inc.

Rochester I Buffalo I Syracuse I Capital District
300 TROLLEY BLVD.
ROCHESTER, NY 14606 www.meengineering.com

M/E PROJECT #: 250032



Drawn By: ZMH

Checked By: NMT

Project Manager: GDD

These documents and all the ideas, arrangements, designs and plans indicated thereon or presented thereby are owned by and remain the property of SWBR and no part thereof shall be utilized by any person, firm, or corporation for any purpose whatsoever except with the specific written permission of SWBR. All rights reserved. ©

Revisions

1 12/12/2025 Addendum #1

COMSTOCK HALL 5TH FLOOR LAB AND SUPPORT SPACE RENOVATIONS 129 Garden Ave, Ithaca, NY 14853

SWBR Project Number 25044.00


Cornell University
Ithaca, NY 14853

MD-101R

PARTIAL FIFTH FLOOR DEMOLITION PLAN -DUCTWORK

11/7/2025100% Construction

Documents



GENERAL NOTES:

A. UNLESS INDICATED OTHERWISE, THE DUCTWORK AT THE VAV AND AIR VALVE INLET AND OUTLET SHALL MATCH THE SIZES SHOWN ON THE EQUIPMENT SCHEDULE.

X DRAWING NOTES:

- 1 PROVIDE CEILING MOUNTED SNORKEL, BALANCE TO 100 CFM. REFER TO DETAILS FOR FURTHER REQUIREMENTS.
- 2 PROVIDE ALL MODIFICATIONS TO EXTEND THE LOW EXHAUST GRILLE TO ACCOMMODATE THE NEW CHASE ENCLOSURE.
- 3 EXISTING FIRE / SMOKE DAMPER SHALL BE TESTED AND CERTIFIED. REFER TO FIRE / SMOKE DAMPER SPECIFICATION FOR FURTHER REQUIREMENTS.


4 TIE DUCTWORK INTO EXISTING. TRANSITION AS REQUIRED TO MAKE THE CONNECTION.

- 5 PROVIDE FIRE WRAP ON THE EXPOSED DUCTWORK TO PROVIDE A CONTINUOUS RATING OF THE 2-HR SHAFT ENCLOSURE.
 6 TIE DUCTWORK INTO AD JUSTABLE HEIGHT ADA FUME HOOD, REFER TO DETAILS FOR CONNECTION
- 6 TIE DUCTWORK INTO ADJUSTABLE HEIGHT ADA FUME HOOD. REFER TO DETAILS FOR CONNECTION REQUIREMENTS.
- 7 PROVIDE AN ACCESS DOOR FOR THE EXISTING FIRE DAMPER.
- 8 BALANCE FUME HOOD TO 485 CFM.9 BALANCE EXHAUST HOOD TO 100 CFM.
- 10 PROVIDE EXHAUST HOOD FOR OWNER PROVIDED LAB EQUIPMENT. REFER TO EXHAUST HOOD
- INSTALLATION DETAIL FOR FURTHER REQUIREMENTS.

 11. ALL NEW EXHALIST DUCTWORK WITHIN LAB 5121A AND 5117B SHALL BE WELDED 304 STAINLESS STEE
- 11 ALL NEW EXHAUST DUCTWORK WITHIN LAB 5121A AND 5117B SHALL BE WELDED 304 STAINLESS STEEL, UNLESS NOTED OTHERWISE.
- 12 TIE DUCTWORK INTO EXISTING FIXED HEIGHT FUME HOOD.
- 13 INSULATE THE EXHAUST DUCTWORK FROM THE CEILING PENETRATION TO THE 5121A WALL PENETRATION.



387 East Main Street Rochester NY 14604 585 232 8300 | rochester@swbr.com SWBR NYS Certificate of Authorization #: 235221



is now Salas O'Brien
Consuling and Engineering
Group of New York, Inc.

Rochester | Buffalo | Syracuse | Capital District
300 TROLLEY BLVD.
ROCHESTER, NY 14606 www.meengineering.com

M/E PROJECT #: 250032



Drawn By: ZMH

Checked By: NMT

Project Manager: GDD

These documents and all the ideas, arrangements, designs and plans indicated thereon or presented thereby are owned by and remain the property of SWBR and no part thereof shall be utilized by any person, firm, or corporation for any purpose whatsoever except with the specific written permission of SWBR. All rights reserved. ©

Revisions

1 12/12/2025 Addendum #1

COMSTOCK HALL 5TH FLOOR LAB AND SUPPORT SPACE RENOVATIONS 129 Garden Ave, Ithaca, NY 14853

SWBR Project Number 25044.00


Cornell University Ithaca, NY 14853

M-101R

PARTIAL FIFTH FLOOR
PLAN - DUCTWORK

11/7/2025 100% Construction

Documents



LILED WATER LOAD SHED		HAI	HARDWARE POINTS SOFTWARE POINTS											
EAM LOAD SHED	CONTROL POINT NAME							<u> </u>			ALARM		NOTES	
EAMLOAD SHED			BO AI	AO	AV	BV	SCF	TRE	BACS		DESCRIPTION	GRAPHIC		
DTAL_EXHAUST AIRFLOW (CFM)	TEAM LOAD SHED					X(6)							BINARY NETWORK INPUT FROM EMCS	
DTAL EXHAUST SETPOINT (CFM)	HILLED WATER LOAD SHED					X(4)							BINARY NETWORK INPUT FROM EMCS	
ABDRATORY AIR CHANGE RATE (ACH)	OTAL EXHAUST AIRFLOW (CFM)				Х			X				Х		
LOW OFFSET SETPOINT (CFM) X BACnet/IP NETWORK POINT OF MIX REPORTED FROM SETPOINT (FCM) X X X X X ARCnet/IP NETWORK POINT NETWORK POI	OTAL EXHAUST SETPOINT (CFM)				Х			X				Х		
LOW OFFSET ACTUAL (CFM) LOW OFFSET ACTUAL (CFM) LOPLY VAV DAMPER POSITION COMMAND LOPLY VAV DAMPER POSITION COMMAND LOPLY VAV AIRFLOW FEEDBACK (CFM) LOPLY VAV AIRFLOW SETPOINT (CFM) LOPLY VAV AIRFLOW SETPOINT (CFM) LOPLY VAV AIRFLOW SETPOINT (CFM) LOPLY VAV POSITION FEEDBACK (%) LOPLY VAV VAIRFLOW SETPOINT (CFM) LOPLY VAV VAIRFLOW FEEDBACK (%) LOPLY VAV VAIRFLOW FEEDBACK (CFM) LOPLY VALVE LORMAND / SETPOINT (CFM) LOPLY VALVE ALARM LOPLY VALVE POSITION COMMAND / SETPOINT (CFM) LOPLY VAIR VALVE POSITION COMMAND / SETPOINT (FF) LOPLY VALVE VAIRFLOW FEEDBACK (CFM) LOPLY VALVE VAIRFLOW FEEDBACK (CFM) LOPLY VALVE VALVE POSITION COMMAND (%) LOPLY VALVE VALVE VALVE VALVE VALVE POSITION COMMAND (%) LOPLY VALVE VALVE VALVE VALVE VALVE POSITION COMMAND (%) LOPLY VALVE VALVE VALVE VALVE VALVE POSITION COMMAND (%) LOPLY VALVE VALV	ABORATORY AIR CHANGE RATE (ACH)				Х			X				Х		
	LOW OFFSET SETPOINT (CFM)				Х							Х		
SUPPLY VAV AIRFLOW FEEDBACK (CFM)	LOW OFFSET ACTUAL (CFM)				Х							Х		
UPPLY VAV AIRFLOW SETPOINT (CFM)	UPPLY VAV DAMPER POSITION COMMAND			Х				X				Х		
UPPLY VAV POSITION FEEDBACK (%) UPPLY AIR VALVE FLOW FEEDBACK (CFM) UPPLY AIR VALVE FLOW FEEDBACK (CFM) X UPPLY AIR VALVE FLOW FEEDBACK (CFM) X UPPLY AIR VALVE POSITION COMMAND / SETPOINT (CFM) X UPPLY AIR VALVE POSITION COMMAND / SETPOINT (CFM) X X X X X X X X X X X X X	UPPLY VAV AIRFLOW FEEDBACK (CFM)				Х			Х	Х		10% FLOW DEVIATION FROM SETPOINT	Х	BACnet/IP NETWORK POINT	
UPPLY AIR VALVE FLOW FEEDBACK (CFM) X	UPPLY VAV AIRFLOW SETPOINT (CFM)				Х			Х				Х	BACnet/IP NETWORK POINT	
UPPLY VALVE ALARM UPPLY AIR VALVE POSITION COMMAND / SETPOINT (CFM) LIFERAT COIL LEAVING AIR TEMPERATURE / SETPOINT (°F) LIFERAT COIL LEAVING AIR TEMPERATURE / SETPOINT (°F) LIFERAT COIL VALVE COMMAND (%) EHEAT COIL VALVE COMMAND (%) EHEAT COIL VALVE COMMAND (%) ENERAL EXHAUST AIR VALVE FLOW FEEDBACK (CFM) LIFERAL EXHAUST AIR VALVE ALARM ENERAL EXHAUST AIR VALVE POSITION COMMAND / SETPOINT (CFM) X X X X X X X X X X X X X X X X X X X	UPPLY VAV POSITION FEEDBACK (%)				Х			Х	Х		VALVE COMMAND ≠ FEEDBACK	Х	BACnet/IP NETWORK POINT	
UPPLY AIR VALVE POSITION COMMAND / SETPOINT (CFM) X	UPPLY AIR VALVE FLOW FEEDBACK (CFM)		Х					Х				Х		
EHEAT COIL LEAVING AIR TEMPERATURE / SETPOINT (°F) X X X X 5°F \(\) ACROSS COIL WITH VALVE COMMANDED CLOSED X X X X 5°F \(\) ACROSS COIL WITH VALVE COMMANDED CLOSED X X X X 5°F \(\) ACROSS COIL WITH VALVE COMMANDED CLOSED X X X X 5°F \(\) ACROSS COIL WITH VALVE COMMANDED CLOSED X X X X X 5°F \(\) ACROSS COIL WITH VALVE COMMANDED CLOSED X X X X X X X X X X X X X X X X X X X	UPPLY VALVE ALARM	Х							Х		FAILURE	Х		
REHEAT COIL VALVE COMMAND (%) SENERAL EXHAUST AIR VALVE FLOW FEEDBACK (CFM) SENERAL EXHAUST AIR VALVE ALARM SENERAL EXHAUST AIR VALVE ALARM SENERAL EXHAUST AIR VALVE POSITION COMMAND / SETPOINT (CFM) XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX	SUPPLY AIR VALVE POSITION COMMAND / SETPOINT (CFM)			Х	Х			Х	Х		10% FLOW DEVIATION FROM SETPOINT	Х		
RENERAL EXHAUST AIR VALVE FLOW FEEDBACK (CFM) X X X X FAILURE RENERAL EXHAUST AIR VALVE ALARM X X X X X X X X X X X X X X X X X X X	EHEAT COIL LEAVING AIR TEMPERATURE / SETPOINT (°F)		Х		Х			Х				Х		
ENERAL EXHAUST AIR VALVE ALARM ENERAL EXHAUST AIR VALVE POSITION COMMAND / SETPOINT (CFM) X X X X X X X X X X X X X X X X X X X	EHEAT COIL VALVE COMMAND (%)			Х				Х	Х		5°F Δ ACROSS COIL WITH VALVE COMMANDED CLOSED	Х		
ENERAL EXHAUST AIR VALVE POSITION COMMAND / SETPOINT (CFM) X X X X X X X X X X X X X X X X X X X	ENERAL EXHAUST AIR VALVE FLOW FEEDBACK (CFM)		Х					Х				Х		
XHAUST FAN MOTOR STATUS (ON/OFF) X X X X X X X X X X X X X X X X X X X	ENERAL EXHAUST AIR VALVE ALARM	Х							X		FAILURE	Х		
XHAUST FAN MOTOR START/STOP UME HOOD SASH POSITION PACE TEMPERATURE / SETPOINT (°F) PACE RELATIVE HUMIDITY (%RH) X X X X X X X X X X X X X	ENERAL EXHAUST AIR VALVE POSITION COMMAND / SETPOINT (CFM)			Х	Х			Х	X	~\\	10% FLOW DEVIATION FROM SETPOINT	Х		
UME HOOD SASH POSITION X X X X X X X X X X X X X	XHAUST FAN MOTOR STATUS (ON/OFF)	Х						Х	x > >		FAILURE	Х		
PACE TEMPERATURE / SETPOINT (°F) PACE RELATIVE HUMIDITY (%RH) X X X X X X X X X X X X X X X X X X X	XHAUST FAN MOTOR START/STOP		Х					Х	7	- 5		Х		
PACE RELATIVE HUMIDITY (%RH) X X X MONITORING ONLY	UME HOOD SASH POSITION		Х					X	x(1	SASH OPEN (18') FOR 24 CONTINUOUS HOURS OR MORE	Х		
	PACE TEMPERATURE / SETPOINT (°F)		Х		×			X	اخ x	7	± 4°F FROM SETPOINT	Х		
PACE OCCUPANCY X X X X X X	PACE RELATIVE HUMIDITY (%RH)		Х					X		$\exists \forall$		Х	MONITORING ONLY	
	PACE OCCUPANCY	Х					Х	X	-{	7		Х		

ROOM NUMBER	DESCRIPTION	ROOM DI	IMENSIONS	COD	E MINIMUI	M VENTILA	ATION		EXHAUST AIR										SUPPLY AIR				
	(NOTE 1)	AREA	HEIGHT	N.	YS	N,	YS	EXHAUST	VALVE	VAL	.VE	OCCL	IPIED	UNOCC	UPIED	SUPPLY	VALVE	VAL	VE	OCC	UNOCC	ALL	
	, ,			OUTI	DOOR	EXH	AUST	POINT	SIZE	RAN	IGE					POINT	SIZE	RAN	NGE			MODE	
				AIRF	LOW	AIRF	LOW	(NOTE 2)								(NOTE 2)						ı	
										MAX	MIN	100 F	-PM	100 l	FPM			MAX	MIN	100 FPM		I	
		(SF)	(FT)	(CFM)	(ACH)	(CFM)	(ACH)			(CFM)	(CFM)	(CFM)	(ACH)	(CFM)	(ACH)			(CFM)	(CFM)	(CFM)	(CFM)	(CFM	
								(E)F-26	-	-	-	685		685		(E)CAV-H5121A	-	-	-	340	340		
5121/5121A	VAV	429	8.0	207	3.6	429	7.5	GEV-5121A	8	800	80	200	15.5	200	15.5	SAV-5121	8	800	80	445	445	-100	
								TOTAL				885		885		TOTAL				785	785	i	

1. THIS REPRESENTS A LABORATORY WHERE THE REQUIREMENTS OF THE FUME HOODS EXCEEDS THE MINIMUM REQUIRED AIR CHANGE RATES ESTABLISHED FOR THE LABORATORY.
2. THE MAX / MIN POSITIONS ON THE VALVE WILL BE SET AT THE FACTORY TO THE FULL FANGE WITH ACTUAL AIRFLOW SET IN SOFTWARE.

1 LAB 5121A CONTROL SCHEMATIC AND SYSTEM SUMMARY NOT TO SCALE

SEQUENCE OF OPERATION

SYSTEM DESCRIPTION

FUME HOOD EXHAUST AIR VALVE (FEV) GENERAL EXHAUST AIR VALVE (GEV) SUPPLY AIR VALVE (SAV) DUCT MOUNTED REHEAT COIL (RHC)

GENERAL

SYSTEM SHALL BE CONTROLLED THROUGH THE BUILDING AUTOMATION AND CONTROL SYSTEM (BACS).

THE BACS SHALL BE CAPABLE OF RETAINING ITS PROGRAMMING AND TIME SETTING DURING A LOSS OF POWER FOR AT LEAST TEN HOURS.

ALL SETPOINTS SHALL BE ADJUSTABLE.

THE BACS SHALL BE CAPABLE OF STARTING AND STOPPING THE SYSTEM FOR SEVEN DIFFERENT DAILY SCHEDULES PER WEEK.

LABORATORY AIR CHANGE RATE ARE BASED ON TOTAL SUPPLY AIRFLOW FROM THE SPACE.

THE SPACE SHALL BE CONTROLLED TO AN AIR CHANGE RATE. THE BACS SHALL CALCULATE THE REQUIRED CFM USING THE ROOM GROSS VOLUME (AREA x CEILING

LOAD SHED: REFER TO LOAD SHED MATRICES FOR THE SYSTEM CONTROL REQUIREMENTS FOR RESEARCH SPACES.

<u>SETPOINTS</u>

SPACE COOLING TEMPERATURE SETPOINTS:

OCCUPIED: $75^{\circ}F \pm 1.5^{\circ}F$ UNOCCUPIED SETBACK: $75^{\circ}F + 3.0^{\circ}F$ UNOCCUPIED: $75^{\circ}F + 6.0^{\circ}F$

SPACE HEATING TEMPERATURE SETPOINTS:

OCCUPIED: 70°F ± 1.5°F UNOCCUPIED SETBACK: 70°F - 3.0°F UNOCCUPIED: 70°F - 6.0°F

MINIMUM LABORATORY OCCUPANCY INDEX TIME: 30 MINUTES

ZONE OCCUPANCY SCHEDULE: 6 AM TO 6 PM, MON-FRI
TOTAL EXHAUST AIR CHANGE RATE (ACPH):

REFER TO LAB AIRFLOW SCHEDULES

ACPH = TOTAL EXHAUST CFM X 60 / ROOM VOLUME

TOTAL EXHAUST AIRFLOW RATE (CFM): GENERAL EXHAUST AIRFLOW RATE + EXHAUST FAN AIRFLOW RATE

SUPPLY AIRFLOW RATE (CFM): REFER TO LAB AIRFLOW SCHEDULE TOTAL EXHAUST AIRFLOW RATE + OFFSET

FUME HOOD EXHAUST AIRFLOW RATE (CFM): REFER TO LAB AIRFLOW SCHEDULE

GENERAL EXHAUST AIRFLOW RATE (CFM):

REFER TO LAB AIRFLOW SCHEDULE

SPACE AIR DIFFERENTIAL OFFSET (CFM)
REFER TO LAB AIRFLOW SCHEDULE

LABORATORY AIRFLOW CONTROL

AIR VALVE POSITIONS SHALL BE BASED ON MODE. UNDER NORMAL CONTROL, ROOM OCCUPANCY SHALL BE DETERMINED VIA ROOM OCCUPANCY SENSORS.

WHEN THE ROOM IS OCCUPIED, THE BACS SHALL SEND AN OCCUPIED COMMAND TO THE FUME HOOD EXHAUST AIR VALVE. THE FUME HOOD MONITOR SHALL INDEX THE FUME HOOD EXHAUST AIR VALVE BETWEEN MINIMUM AND MAXIMUM POSITIONS AS NEEDED TO MAINTAIN THE OCCUPIED FACE VELOCITY SETPOINT BASED ON THE SASH POSITION. THE POINT EXHAUST AIR VALVE SHALL MODULATE AS NEEDED TO MAINTAIN THE SETPOINT. THE SUPPLY AIR VALVE SHALL MODULATE AS NEEDED TO MAINTAIN THE SPECIFIED AIRFLOW DIFFERENTIAL.

WHEN THE ROOM IS UNOCCUPIED, AND THE SASH IS AT OR BELOW 18-INCHES, THE BACS SHALL SEND AN UNOCCUPIED COMMAND TO THE FUME HOOD EXHAUST AIR VALVE. THE FUME HOOD MONITOR SHALL INDEX THE FUME HOOD EXHAUST AIR VALVE BETWEEN MINIMUM AND MAXIMUM POSITIONS AS NEEDED TO MAINTAIN THE SETPOINT BASED ON THE SASH POSITION. THE POINT EXHAUST AIR VALVE SHALL MODULATE AS NEEDED TO MAINTAIN THE AIRFLOW SETPOINT. THE SUPPLY AIR VALVE SHALL MODULATE AS NEEDED TO MAINTAIN THE SPECIFIED AIRFLOW DIFFERENTIAL.

WHEN THE ROOM IS UNOCCUPIED AND THE FUME HOOD SASH IS ABOVE 18-INCHES, THE BACS SHALL NOT SEND THE SPACE UNOCCUPIED COMMAND TO THE FUME HOOD EXHAUST AIR VALVE. THE FUME HOOD MONITOR SHALL INDEX THE FUME HOOD EXHAUST AIR VALVE TO MAINTAIN THE OCCUPIED SASH OPEN AIRFLOW SETPOINT. THE POINT EXHAUST AIR VALVE SHALL MODULATE AS NEEDED TO MAINTAIN THE AIRFLOW SETPOINT. THE SUPPLY AIR VALVE SHALL MODULATE AS REQUIRED TO MAINTAIN THE SPECIFIED AIRFLOW DIFFERENTIAL.

VACANT MODE: THE BACS SHALL SEND A DECOMMISSION COMMAND TO THE FUME HOOD EXHAUST AIR VALVE. THE FUME HOOD MONITOR SHALL INDEX THE FUME HOOD EXHAUST AIR VALVE TO CLOSE. THE POINT EXHAUST AIR VALVE SHALL MODULATE AS NEEDED TO MAINTAIN AIRFLOW SETPOINT. THE SUPPLY AIR VALVE SHALL MODULATE AS REQUIRED TO MAINTAIN THE SPECIFIED AIRFLOW DIFFERENTIAL.

REGARDLESS OF THE OCCUPANCY MODE, ALL THE SUPPLY AND EXHAUST AIR VALVES SHALL COMMAND CLOSED UPON ACTIVATION OF THE MANUAL VENTILATION SHUTDOWN

ZONE TEMPERATURE CONTROL

TEMPERATURE SETPOINTS SHALL BE DETERMINED BASED ON A COMBINATION OF PROGRAMMED SCHEDULE AND SPACE OCCUPANCY SENSORS.

OCCUPIED HEATING: IF THE SPACE IS OCCUPIED DURING THE SCHEDULED OCCUPIED PERIOD AND THE SPACE TEMPERATURE FALLS BELOW THE OCCUPIED HEATING TEMPERATURE SETPOINT, THE REHEAT CONTROL VALVE SHALL MODULATE TO MAINTAIN THE SPACE TEMPERATURE SETPOINT. WHEN THE SPACE TEMPERATURE IS AT SETPOINT,

OCCUPIED COOLING: IF THE SPACE IS OCCUPIED DURING THE SCHEDULED OCCUPIED PERIOD AND THE SPACE TEMPERATURE RISES ABOVE THE OCCUPIED COOLING TEMPERATURE SETPOINT, THE REHEAT COIL CONTROL VALVE SHALL CLOSE.

OCCUPIED SETBACK: IF THE SPACE BECOMES UNOCCUPIED DURING THE SCHEDULED OCCUPIED PERIOD, THE ABOVE OCCUPIED HEATING/COOLING SEQUENCE SHALL APPLY, BUT THE SPACE SHALL BE MAINTAINED AT THE OCCUPIED SETBACK TEMPERATURE SETPOINT.

THE REHEAT COIL CONTROL VALVES SHALL BE CLOSED.

UNOCCUPIED HEATING: IF THE SPACE IS UNOCCUPIED DURING THE SCHEDULED UNOCCUPIED PERIOD AND THE SPACE TEMPERATURE FALLS BELOW THE UNOCCUPIED HEATING TEMPERATURE SETPOINT, THE ABOVE OCCUPIED HEATING SEQUENCE SHALL APPLY, BUT THE SPACE SHALL BE MAINTAINED AT THE UNOCCUPIED HEATING TEMPERATURE SETPOINT.

UNOCCUPIED COOLING: IF THE SPACE IS UNOCCUPIED DURING THE SCHEDULED UNOCCUPIED PERIOD AND THE SPACE TEMPERATURE RISES ABOVE THE UNOCCUPIED COOLING TEMPERATURE SETPOINT, THE ABOVE OCCUPIED SETBACK SEQUENCE SHALL APPLY, BUT THE SPACE SHALL BE MAINTAINED AT THE UNOCCUPIED COOLING TEMPERATURE SETPOINT AND THE REHEAT COIL CONTROL VALVE SHALL CLOSE.

IF THE ZONE BECOMES OCCUPIED DURING THE SCHEDULED UNOCCUPIED PERIOD, THE OCCUPIED HEATING/COOLING SEQUENCES SHALL APPLY FOR THE DURATION OF OCCUPANCY. THE ZONE SHALL BE MAINTAINED AT THE OCCUPIED TEMPERATURE SETPOINTS. WHEN THE ZONES BECOMES UNOCCUPIED AGAIN DURING THE SCHEDULED UNOCCUPIED PERIOD, THE ZONE SHALL INDEX BACK TO UNOCCUPIED MODE

VACANT MODE: THE ABOVE UNOCCUPIED HEATING/COOLING SEQUENCE SHALL APPLY, BUT THE SPACE SHALL BE MAINTAINED AT THE UNOCCUPIED SETBACK TEMPERATURE

SWBR

387 East Main Street Rochester NY 14604 585 232 8300 | rochester@swbr.com SWBR NYS Certificate of Authorization #: 235221



is now S Salas O'Brien
Consulting and Engineering
Group of New York, Inc.

Rochester | Buffalo | Syracuse | Capital District
300 TROLLEY BLVD.
ROCHESTER, NY 14606 www.meengineering.com

M/E PROJECT #: 250032



Drawn By: NMT

Checked By: NMT

Project Manager: GDD

These documents and all the ideas, arrangements, designs and plans indicated thereon or presented thereby are owned by and remain the property of SWBR and no part thereof shall be utilized by any person, firm, or corporation for any purpose whatsoever except with the specific written permission of SWBR. All rights reserved. ©

Revisions
1 12/12/2025 Addendum #1

COMSTOCK HALL 5TH FLOOR LAB AND SUPPORT SPACE RENOVATIONS 129 Garden Ave,

SWBR Project Number 25044.00


Cornell University

Ithaca, NY 14853

Ithaca, NY 14853

M-402R

AND SYSTEM SUMMARIES



387 East Main Street Rochester NY 14604 585 232 8300 | rochester@swbr.com SWBR NYS Certificate of Authorization #: 235221



Rochester | Buffalo | Syracuse | Capital District 300 TROLLEY BLVD. 585.288.5590 ROCHESTER, NY 14606 www.meengineering.com M/E PROJECT #: 250032

Checked By: Project Manager: GDD These documents and all the ideas, arrangements designs and plans indicated thereon or presented thereby are owned by and remain the property of SWBR and no part thereof shall be utilized by any person, firm, or corporation for any purpose whatsoever except with the specific written permission of SWBR. All rights reserved. ©

Revisions

1 12/12/2025 Addendum #1

COMSTOCK HALL 5TH FLOOR LAB AND SUPPORT SPACE RENOVATIONS 129 Garden Ave, Ithaca, NY 14853

SWBR Project Number 25044.00

Cornell University Ithaca, NY 14853

M-500R **DETAILS - HVAC**

COMSTOCK HALL 5TH FLOOR LAB AND SUPPORT SPACE RENOVATION RFI Form

RFI/ Response	Page/ Dwg./Spec./Rep.	Section/		Design Team
Index	Number	Paragraph/Topic	RFI	Response
1			Due to holidays and man power issues. Asking for 1 week bid extension.	See Addendum No. 1, Item 1. Final RFIs date and Bid date have been extended.
2	AD-101		Outside of room 5123B on Drawing AD-101, there is a section of the wall that is hatched for removal. There is nothing noted on the drawing for removal. There is nothing shown/noted on the new plan for this location, and the elevation drawing states that the electrical panel here is existing to remain. Please advise if there is any work to be done here.	See Addendum No. 1, Item 7. Existing electric panel to remain. No work to be done here.
3	AD-101		Drawing note 22 does not appear to show on the doorway of room 5119, but drawing note 23 appears in the corridor past this doorway. Please advise if this door also needs the Remedi8 label.	See Addendum No. 1, Item 7. Keynote 22 added to existing door of Room 5119
4			What prep is required of the existing epoxy floor for the new resinous floor?	Manufacturer rep recommended sounding out existing floor to identify and remove unbonded areas. Pre-flash low areas with epoxy mortar. Mechanically prepare entire floor surface via sanding or dustless grinding process. Primer is required if not a Stonhard product.
5			Is the job ready to begin as soon as the contract is in place?	Yes, On-site mobilization is anticipated to begin at the end of January / beginning of February, 2026.
6			Is there a place to put a dumpster?	The dumpster can be located at the Comstock Hall loading dock, access by the service drive from Campus Road.