

ADDENDUM NO. 1

August 20, 2020

This Addendum contains changes to the requirements of the Contract Documents and Specifications. Such changes are to be incorporated into the Construction Documents and shall apply to the work with the same meaning and force as if they had been included in the original document. Wherever this Addendum modifies a portion of a paragraph of the specifications or a portion of any Drawing, the remainder of the Paragraph or Drawing shall remain in force.

NOTE: Provisions of all Contract Documents apply.

Item 1. Attached is the Pre-Bid Sign-in Sheet for reference only.

DRAWINGS

Item 2. Drawing C-001, Phasing, Code & Building Permit Notes

DELETE Note 3.0 in its entirety.

REPLACE with

THE CONTRACTOR SHALL OBTAIN, MAINTAIN AND PAY FOR ALL PERMITS AND LICENSES NECESSARY FOR THE EXECUTION OF THE WORK AND FOR THE USE OF SUCH WORK WHEN COMPLETED. SUCH PERMITS SHALL INCLUDE BUT ARE NOT LIMITED TO BUILDING, ELECTRICAL, PLUMBING, BACKFLOW PREVENTION, DIG SAFE, FILL, STREET USE AND BUILDING DEMOLITION.

Item 3. RFI Questions and Clarifications

See attached RFI Log (Items 1-3).

Attachments: Pre-Bid Sign-in Sheet
RFI Log (1-3)

******END OF ADDENDUM******

RFI Form

RFI/ Response Index	Page/ Dwg./Spec./Rep. Number	Section/ Paragraph/Topic	RFI	Design Team Response
1			<p>Concrete Work In front of Trench Drain</p> <p>It was discussed at the pre-bid walk through that the concrete work at the existing trench drain will end up pitching water away from the drain. The sidewalk panels that create a tripping problem were three panels all the way to the west end of the group. Should we replace the concrete as shown and pitch the water away from the drain or do something else?</p>	<p>The work shall be Bid for replacement as shown. Any changes will be addressed through the Change Order process and will utilize Unit Prices as applicable.</p>
2			<p>West Entrance to Gannette</p> <p>The west entrance to Gannette (western most spot in the clouded area on C-101) calls for removal and replace of concrete sidewalk on the Gannette side of the granite. In order to make this entrance ADA accessible the concrete panels on the opposite side of the granite will need to be removed and replaced at a slightly higher elevation. Please advise if this should be added to the project?</p>	<p>The work shall be bid as shown. Any changes will be addressed through the Change Order process and will utilize Unit Prices as applicable.</p>
3			<p>Demo note 4 on C-101 calls to remove and dispose of broken granite pavers. Improvement note 4 does not call for new pavers, is this intended to be covered by the unit price or do some new pavers need to be covered under base bid to repair what is removed?</p>	<p>In all cases where removal and disposal are noted, the Contractor shall provide new granite.</p>