

CORNELL UNIVERSITY
FACILITIES CONTRACTS
121 HUMPHREYS SERVICE BUILDING
ITHACA, NEW YORK 14853-3701

PAUL SCHOELLKOPF HOUSE MEN'S LACROSSE
LOCKER ROOM RENOVATION

ADDENDUM NO. 2

June 7, 2022

This Addendum contains changes to the requirements of the Contract Documents and Specifications. Such changes are to be incorporated into the Construction Documents and shall apply to the work with the same meaning and force as if they had been included in the original document. Wherever this Addendum modifies a portion of a paragraph of the specifications or a portion of any Drawing, the remainder of the Paragraph or Drawing shall remain in force.

NOTE: Provisions of all Contract Documents apply.

Item 1. RFI Questions and Clarifications

See attached RFI Log (Item 11)

Attachments: RFI Log (Items 1-11)

******END OF ADDENDUM******

RFI Form

RFI/ Response Index	Page/ Dwg./Spec./Rep. Number	Section/ Paragraph/Topic	RFI	Design Team Response
1	A-102		Can shop drawings be provided for guidance on installation of owner furnished casework.	The vanity, TV cabinet, and casework in 109 to be installed by BSports. Lockers are to be installed by Contractor. Shop drawings will be provide for locker installation.
2	A-103		A-103, Note #4: Can this note please be handled via allowance so we are all carrying the same value? Not exactly sure what to figure as this note is not clear and could be very minimal work but could also be extensive work.	See Addendum No. 1, Item 1.
3	A-104		A-104, Note #4: Please provide a detail for this.	Provide 12' x 7' x 1 1/2" deep galvanized metal pan sloped to outlet. Provide 3" high leg at exterior wall. Attach with hit pins and sealant at top edge. Provide straps at other side and attach to beams. Provide clear plastic line and drain into floor drain in toilet space.
4	A-102		Please confirm the design intent for cast underlayment is limited to minor skim coating of existing floor.	Yes, this will be minor skim coating of the floors, if needed.
5	E-103 & E-104		1. B-1 LED light tape in owner supplied lockers. a. Are the LED lights integral to the locker assembly, or are they to be purchased as part of the lighting package? b. The supplied part number does not provide enough information to determine the fixture mounting method or whether or not the leads are attached to 2' section of LED tape. c. E-103 Keyed Note #1 calls for a proximity contact on the door to operate the light. Please verify whether or not this feature is not provided by the locker manufacturer. d. Is the proximity contact supposed to switch the power coming from the driver to the LED tape, or from the 120VAC lighting circuit to the driver? e. The (8) lockers in room #102 are not shown on Drawing E-103. Will these lockers have LED tape lights? If they have lights, what circuit will feed the lights? 2. Are the USB receptacles in the lock assembly completely wired with a device box, cover, and feed cable, so that the labor and material required is to connect to the provided cable? 3. There is no circuit designated for the USB receptacles in the (5) lockers on the east wall of room #105 on drawing E-104. What circuit will feed these lockers?	1) a. & b. See Addendum No. 1, Item 2. The LED lights will be part of the locker assembly and provided by the manufacturer. c.&d. See Addendum No. 1, Item 6. Locker assembly to be provided by manufacturer. Revised note to remove mention of proximity sensor. e. Lockers in room 102 will not have LED light fixtures, but will have USB receptacles. 2) USB receptacles, box, and cover are provide by the manufacturer as part of the locker assembly. Power wiring and conduit from the serving panel will need to be provided as indicated on E-104 keyed renovation note 2. 3) See Addendum No. 1, Items 7. Lockers in room 105 on the east wall will be powered by circuit LNP-11 SECTION 3-3.
6	Pre-Bid Mtg		Where is the dumpster location?	A possible location for the dumpster would be adjacent to the exterior, Northeast corner of Hoy Garage.
7	Pre-Bid Mtg		Do you have an ETA of delivery for Owner furnished items.	Approximately 8 weeks for delivery from BSport Custom Lockers. Order/delivery date shall be coordinated with the Contractor.
8	Pre-Bid Mtg		Is Note 10 on page A-101 applicable for Room 110?	It is the Contractor's decision.
9	Pre-Bid Mtg		Do you have an idea of the restoration that will be required for the stairs?	The existing wooden stair treads shall be restored in a manner as to provide a stable, level walking surface without blemishes, cracks or fissures, (and have a service life of 10 years, minimum.)
10	Pre-Bid Mtg		Do you have an idea of whether the lighting is specialty that carries long leads?	No long lead times.
11	M-101 & M-102		Key Notes 5/M101 & 15/M102 call for the replacement of exhaust fan PV-2 but do not mention if the existing curb is to be replaced. Should I assume that the curb is being replaced and therefor would need to be flashed into the existing roof system?	The existing curb is to remain in place.