

ADDENDUM NO. 2

February 11, 2022

This Addendum contains changes to the requirements of the Contract Documents and Specifications. Such changes are to be incorporated into the Construction Documents and shall apply to the work with the same meaning and force as if they had been included in the original document. Wherever this Addendum modifies a portion of a paragraph of the specifications or a portion of any Drawing, the remainder of the Paragraph or Drawing shall remain in force.

NOTE: Provisions of all Contract Documents apply.

SPECIFICATIONS

Item 1. Specification Section 06 10 00 Rough Carpentry

ADD to the end of paragraph 1.3A, “(Council is recommended, but not required.)”

DRAWINGS

Item 2. Drawing A-001, Index of Drawings and General Information

DELETE drawing A-001

REPLACE with revised drawing A-001R, attached.

Item 3. Drawing FP-001, Sprinkler Notes, Symbols, and Details, SPRINKLER SCOPE OF WORK

ADD Note 22

22. Paint all new exposed sprinkler system piping and hangers in finished spaces to match existing paint finishes in the area. Paint after system is inspected, tested, and approved by Jensen Hughes, Cornell EH&S, Ithaca Fire Department, and City of Ithaca Building Division.

Item 4. Drawing FP-002, Sprinkler Phasing Plan, PHASING NOTES:

ADD Note 7.7

7.7. Paint all new exposed sprinkler system piping and hangers in finished spaces to match existing paint finishes in the area. Paint after system is inspected, tested, and approved by Jensen Hughes, Cornell EH&S, Ithaca Fire Department, and City of Ithaca Building Division.

Rockefeller Hall Sprinkler System Replacement
Addendum No. 2
February 11, 2022
Page 2

Item 5. RFI Questions and Clarifications

See attached RFI Log (Items 1 – 9).

Attachments: Drawing A-001R
RFI Log (1-9)

******END OF ADDENDUM******