

ADDENDUM NO. 3

August 29, 2023

This Addendum contains changes to the requirements of the Contract Documents and Specifications. Such changes are to be incorporated into the Construction Documents and shall apply to the work with the same meaning and force as if they had been included in the original document. Wherever this Addendum modifies a portion of a paragraph of the specifications or a portion of any Drawing, the remainder of the Paragraph or Drawing shall remain in force.

NOTE: Provisions of all Contract Documents apply.

Item 1. Specification change – SECTION 321400 – UNIT PAVING

DELETE the following references to granite stone benches:

Paragraph 1.2 - Summary, item A.4
Paragraph 1.4 - Submittals, item D.6

Item 2. SECTION 321400 – UNIT PAVING, paragraph 2.2 – Stone Materials, B.

DELETE item B header:

“B. Granite for new benches around flagpole and for new flagpole lighting pedestals”, in its entirety.

REPLACE with

“B. Granite for new flagpole lighting pedestals”

Item 3. Drawing M001 – PH. 2 MECHANICAL SYMBOLS, NOTES, & SCHEDULES,
- INSULATION SCHEDULE.

ADD two (2) new rows:

<u>Type</u>	<u>Pipe and Fitting Insulation Type</u>
Ductwork.	No Insulation Required on Ductwork
Storm Piping.	No Insulation Required on Storm Piping

Item 4. Questions and Clarifications – See attached RFI Log Item (6)

Attachments: RFI Log items (1-6)

******END OF ADDENDUM******

RFI Form

RFI/ Response Index	Page/ Dwg./Spec./Rep. Number	Section/ Paragraph/Topic	RFI	Design Team Response
1	INS-5	14 c.	We are receiving feed back from the subcontractor community that they are currently focused on finishing existing summer work/contracts for K-12 and higher education clients and do not currently have time to bid jobs. Due to this it looks like sub contractor bid coverage is going to be poor which will likely result in poor bid pricing. We are requesting a bid extension to the week of 8/11 (but not on a Monday).	See Addendum No. 1, Item 1 for revised bid date.
2	FR4.50	Structural Details	Existing Tunnel Mortar Question Welliver Bidder, Welliver McGuire, Inc., 08.22.2023 09: 51 AM Eastern Time Detail 2/FR4.50 shows two pictures. The picture on the right is of the interior stone masonry in the tunnel. The bottom note says to remove the mortar to a depth of four inches prior to concrete placement. Does this mean that at every joint, we are to remove four inches of mortar at the entire length of the tunnel? Please advise..	Remove stone to provide 3 inch minimum bearing and remove mortar joints to depth of 4 inches for entire length of new concrete slab
3	FR1.01	Structural Details	New Slab Thickness Welliver Bidder, Welliver McGuire, Inc., 08.22.2023 10: 05 AM Eastern Time Can you please confirm the new slab thickness? Detail 2/FR1.01 shows a 9" thick assembly and detail 3/FR4.50 shows a 7" thick slab with a 12" x 16"/6" haunch.	Slab thickness is per details in FR4.50
4	FR1.01	First Floor Structural Plan	Partial Width Concrete Slab Repair Question Welliver Bidder, Welliver McGuire, Inc., 08.22.2023 10: 09 AM Eastern Time Note S2 on drawing FR1.01 says that we are to assume 100 SF of repair for partial slab repairs. How many locations are we to assume (1 location of 100 SF, 2 locations of 50 SF, 10 locations of 10 SF, etc.)? The number of locations dramatically affects productivity, saw cuts/joints, etc.	Only 2 areas of slab are scheduled to remain after demolition where repairs will be made. For the purposes of the bid assume that the 100SF will be used in two locations. Exact size of concrete repair cannot be determined at this time.
5			Concrete Topping Question Welliver Bidder, Welliver McGuire, Inc., 08.22.2023 10: 13 AM Eastern Time Please confirm that the sloped concrete topping is to be placed over the entire length of the War Memorial, including the S2 sections, and that the existing concrete slab to remain will not impact the elevation of the concrete topping.	Sloped concrete topping is to be placed over the entire length of the new and remaining existing concrete slab. The concrete topping on the original slab that is remaining is to be removed.
6	FR1.01B	Spec section Unit Paving 32 14 00	6 Granite Benches Welliver Bidder, Welliver McGuire, Inc., 08.25.2023 08:44 AM Question The specification for Unit Paving (32 14 00) calls out granite benches around the flagpole. However, they are not shown on the drawings. Were these removed? Should they be added to the drawings? Please advise	See Addendum No. 3, item 1. Stone benches are removed from the project