

BID ADDENDUM NO. 6

May 30, 2018

Elmira City School District
Ernie Davis Academy 2018 Additions & Alterations
HUNT No.: 2012-211

SED #07-06-00-01-0-038-026

The following Addendum items shall be considered a part of the contract documents prepared by HUNT ENGINEERS, ARCHITECTS & LAND SURVEYORS; P.C., Bid Document date of June 29, 2017; issued for bid April 25, 2018.

Clarifications issued by this Addendum:

1. Integrator noted on "T" series drawings shall be provided by Owner.

Revisions to Drawings issued by this Addendum:

ITEM AD6-1 Refer to Drawings A0.12 & 0.13, Floor Demolition Plans

AMEND Demolition Note D2 to read, "General Contractor to saw cut and remove existing slab on grade and to trench, backfill and compact trench to accommodate new plumbing piping. Plumbing Contractor to install new plumbing piping in trench. General Contractor to patch and prepare surface for new construction. Trench location shown on drawing is for reference only and shall not be scaled. Plumbing contractor shall determine required trench width and depth needed to obtain proper slope. General Contractor to coordinate saw cut area with Plumbing Contractor. Provide floor slab repair per detail 18/S3.1."

ITEM AD6-2 Refer to Drawings A0.12 & 0.13, Floor Demolition Plans

AMEND Demolition Note D3 to read, "General Contractor to saw cut and remove existing slab on grade, and to trench, backfill and compact trench to accommodate new electric @ aisle lighting trench. Electrical Contractor to install new conduit & recessed floor boxes in trench. General Contractor to patch and prepare surface for new construction. Trench location shown on drawing is for reference only and shall not be scaled. Elec. Contractor shall determine required trench width and depth. General Contractor to coordinate saw cut area with Elec. Contractor. Provide floor slab repair per detail 18/s3.1."

ITEM AD6-3 Refer to Drawing A5.7, Enlarged Auditorium Plan

AMEND Auditorium Drawing Note 8 to read, "Electrical Contractor to install power supplies (provided by others) to power led aisle lights for pathway lighting. Provide aisle lighting in locations shown. Provide 18" flexible conduit whip with 3/8" NPT male connection. EC will provide a flush mounting box with 3/8" NPT female cover, all in-slab wires, and conduits. Turn

power supply over to EC for installation. Provide 2-#12, 1-#12 EG in 3/4" conduit from dimmer rack power supply box. Run conduit and wires buried in floor to recessed box (provided by EC) flush mounted in floor below chair. Junction box shall be centered below chair and 8" from edge of aisle to center of box (14" for cantilever ends) and 4" from back of chair arm to center of box. Provide flex connection from recessed box to arm chair. This box and chair connection is typical at each chair located on the aisle (92 locations). Provide switch and field locate switch per Architect/Owner instruction. Connect seat lights to panel stage 3.

ITEM AD6-4 Refer to Drawings T1.2 – T1.10, Technology Plans

AMEND Drawing Note 1 to read: "Provide backbox and conduit for projector and DAV wiring at locations indicated and as shown in detail 8/T2.1. Projector and wiring between devices shall be furnished and installed by Owner."

ITEM AD6-5 Refer to Drawings T1.2 – T1.10, Technology Plans

AMEND Drawing Note 1 to read: "Provide backbox and conduit for DAV wiring at locations indicated and as shown in detail 8/T2.1. DAV faceplate and wiring between devices shall be furnished and installed by Owner."

End of Addendum (6)