



IBI GROUP
3rd Floor, 59-61 Court Street
Binghamton NY 13901 USA
tel 607 772 0007 fax 607 723 4121
ibigroup.com

DATE: February 14, 2020
TO: All Planholders
SUBJECT: **ADDENDUM NO. 5**
PROJECT: Maine Endwell Central School District
2019 Capital Improvements – Phase 1
IBI Reference No. 121341

SED REVIEW NOS. 19-0750, 19-0751, 19-0752, 19-0753, and 19-0754

SED PROJECT NOS.

03-11-01-06-0-001-018 – Homer Brink Elementary
03-11-01-06-0-008-017 – Maine Memorial Elementary
03-11-01-06-0-010-025 – Senior High School
03-11-01-06-0-015-017 – Middle School
03-11-01-06-5-003-009 – Bus Garage

All contractors submitting proposals for the above project shall take note of the following changes, additions, interpretations, clarifications, etc., in connection with the bidding documents.

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated October 15, 2019, and any previously issued addenda, as noted below.

Previous Issued Addenda

Addendum No. 4 – February 13, 2020
Addendum No. 3 – February 12, 2020
Addendum No. 2 – February 7, 2020
Addendum No. 1 – February 3, 2020

Index to Addendum

IBI Group

Pages

AD5-1 - 2

Attachments

None

I. ADDENDUM NO. 4

A. Part I. Addendum No. 3:

1. Paragraph A, Item 4, Sub-Item a., delete “71” x 48” x 36” in its entirety and insert “72” x 48” x 36” in lieu thereof.

II. SPECIFICATIONS

A. Section 10 11 01 – Visual Display Boards:

1. Question: Section 10 11 01, regarding Homer Brink Elementary School, Addenda 3 clarified the sizes of MB-4 and MB-5 – can you also advise to the dimensions of MB-1, MB-2, and MB-3?

a. **Clarification:**

Display Board Schedule, Homer Brink ES:

MB-1 = 4'-0"H x 8'-0"W Marker Board

MB-2 = 4'-0"H x 4'-0"W Marker Board (Speech 112, Speech 112.1, Reading 112.2, Reading 112.3)

MB-2 = 4'-0"H x 8'-0"W Marker Board with Staff Lines (Music Room G-16)

MB-3 = 4'-0"H x 4'-0"W Tack board w/ 4'x8' Marker Board

MB-4 = 4'-0"H x 6'-0"W Marker Board

MB-5 = 4'-0"H x 5'-0"W Marker Board

B. Section 10 14 23 – Room-Identification Signage:

1. Question: What is the quantity of room signs?

- a. **Clarification:** Room signage shall be provided at Homer Brink ES at all locations where indicated by keyed renovation note A3. In addition, provide (1) ADA/ANSI A117.1 compliant room sign at Middle School FCS M118 and (2) compliant room signs at High School Toilets 114 and 116, to be included in the respective alternates for renovation of those spaces.

III. DRAWINGS

A. Drawing HB-A105 – First Floor Renovation Plan – Area A:

1. Question: Was the Sun Control Window Film called out anywhere or is the Corridor 1-5 panes on drawing HB-A105 where these are getting applied? I did not see the actual callout anywhere on the drawings for a note 10. Just trying to confirm where they would like the Prestige 40 solar control applied. Please clarify.
- a. **Clarification:** General Renovation Note 10 shall apply to all existing vision glazing scheduled to remain throughout the building. Note 10 excludes glazing located in Corridor 1-5 from this scope of work.

B. Drawing HB-A200 – Building Elevations:

1. Question: What are the dimensions of the logo signage on HB-A200?
- a. **Clarification:** Large "Spartan Head" logo shall be 12'-0" tall x approx. 10'-6" wide, small "ME" logo shall be 2'-0" tall x approx. 2'-9" wide.

C. Drawing HB-E203 – Partial First Floor Power Renovation Plan Area A:

1. **Clarification:** The Electrical Contractor is responsible to connect magnetic door holders provided by the G.C. to the fire alarm system. Holders are to release the doors when the fire alarm system is activated. Base bid work will consist of door 1-3, shown on HB-A105.

END OF ADDENDUM