

Newfield Central School District
Capital Project – Phase III Additions & Alterations
HUNT 2712-008
SED Number: 61-09-01-04-0-001-017
61-09-01-04-0-005-013

ADDENDUM NO. 5

July 5, 2018

The following Addendum (Addenda) shall be considered a part of the contract documents prepared by HUNT EAS; P.C. dated June 23, 2017, Issued for Bid May 29, 2018.

Project Manual Sections Issued by this Addendum:

None

Drawings Issued by this Addendum:

None

Clarifications:

HC contractor is responsible for removing all existing piping and providing new piping in High School Mechanical Room 126 per detail 23/HS-H4.2. Tie-in point to (2) existing 5” mains from Elementary School (scheduled to remain) shall be at plan South wall.

Revisions to Project Manual:

ITEM AD 5-1 Refer to Specification Section 06 41 00 – Architectural Wood Casework

AMEND paragraph 2.5, C to read: “Plastic Edge Banding: 3 mm extruded PVC, convex shaped, smooth finish, applied with hot glue; width to match component thickness.”

Revisions to Drawings:

ITEM AD 5-2 Refer to Drawing ES-A1.1 – PARTIAL FIRST FLOOR PLAN AREA “A”

ADD note to detail 2/ES-A1.1 to read: “Provide 3/4” plywood to panels (top, bottom, shelving) 36” or less. Provide 1” plywood for panels over 36”.