



**DESIGN AND CONSTRUCTION GROUP
THE GOVERNOR NELSON A. ROCKEFELLER
EMPIRE STATE PLAZA
ALBANY, NY 12242**

ADDENDUM NO. 2 TO PROJECT NO. 46130

**CONSTRUCTION, HVAC, PLUMBING AND ELECTRICAL WORK
PROVIDE CLASSROOMS & OFFICE SPACE, BLDG. #38
RESIDENTIAL REHABILITATION UNIT
CAYUGA CORRECTIONAL FACILITY
2202 STATE ROUTE 38A, RT 38A.
MORAVIA, NEW YORK**

February 28, 2020

NOTE: This Addendum forms a part of the Contract Documents. Insert it in the Project Manual. Acknowledge receipt of this Addendum in the space provided on the Bid Form.

CONSTRUCTION WORK DRAWINGS

1. Drawing No. A-110:
 - a. Revise key note 2 on drawing to read: PERIMETER FLOOR TRENCH. PROVIDE 1/8" STAINLESS STEEL PLATE FLOOR COVER WITH 3/8" COUNTER SUNK SECURITY TORX EXPANSION ANCHORS @ 12" O.C. SEAL PERIMETER WITH TYPE 6 SEALANT. SEE DETAILS 6 AND 7 ON SHEET A-501.

2. Drawing No. A-401:
 - a. REVISE NOTE 1. TO READ;
PREPARE EXISTING CONCRETE FLOOR SLAB FOR ECT FLOOR FINISH AS RECOMMENDED BY THE MANUFACTURER. INCLUDING, BUT NOT LIMITED TO, INFILLING CRACKS (300LF +/-) AND LEVELING AND PITCHING (5500SF +/-) TO DRAINS WITH COMPATIBLE APPROVED PRODUCTS BY THE EPOXY RESIN FLOORING MANUFACTURER.

 - b. Revise ROOM FINISH SCHEDULE, REPLACE FLOOR FINISHES INDICATED AS 'SEAL' WITH 'ECT'.

END OF ADDENDUM

Erik T. Deyoe, P.E.
Director, Division of Design
Design & Construction