

SECTION 01 91 13.03

ADDENDUM

Watkins-Montour Regional Wastewater Treatment Facility
Contract No. 2, Regional Wastewater Treatment Facility
CWSRF Project No. C8-6423-03-00
Addendum No. 3
Date Issued: February 5, 2018

The attention of bidders is called to the following changes to the Bid Documents, shall be taken into account in the preparation of Bids, and shall be a part of the Bid Documents

Bidders must acknowledge receipt of this Addendum on page 1 of the Bid Form.

PROJECT MANUAL

| <u>Section</u> | <u>Description</u> |
|----------------|--|
| 00 73 16 | Article 5, REVISE Paragraph 5.03.1.C. "The Technical Data contained in such report upon whose accuracy Contractor may rely are boring logs, laboratory tests, <u>field measurements, and photographs</u> . The GDR is contained within these Contract Documents." |
| 26 32 13 | DELETE Paragraph 2.5.3 in its entirety. |

DRAWINGS

| <u>Drawing</u> | <u>Description</u> |
|----------------|---|
| E-101 | ADD General Note 10.: "CONTRACT 2B CONTRACTOR SHALL FURNISH AND INSTALL AN ADDITIONAL 50 LF OF 1-1/2" BURIED CONDUIT AND PULL STRING ON THE EAST SIDE OF THE ADMINISTRATION BUILDING AND TERMINATED THROUGH THE FLOOR SLAB IN ROOM 103 (UTILITIES) FOR ACCOMMODATION OF ELECTRICAL ANTENNAE CABLE. CABLE WILL BE FURNISHED AND INSTALLED BY CONTRACT 1B CONTRACTOR." |
| 26 32 13 | DELETE Paragraph 2.5.3 in its entirety. |

CLARIFICATIONS

No. Description

Q1 M-301, Modular Boiler Detail, Note 1; "Boiler to be mounted and installed in accordance with manufacturer's instructions. Combustion air and venting per manufacturers instructions. Work by Contract 1B." What is Contract 1B referring to and what work is this? Setting of boiler and combustion air and venting? Should Contract 1C plan on doing this work and disregard the note for Contract 1B to perform work?

A1 Building heating systems to be by HVAC Contract 2C. This clarification supersedes the clarification issued under Addendum No. 2.

Q2 The geotech report From Haley and Aldridge states that the groundwater elevation is 446-448.5, but the borings show groundwater elevations substantially different, ie 442.5, 435, 436, 435 respectively. Why does the H&A report state different elevation than what is represented in the? boring log

A2 Table 3-1 of the GDR includes water level data that are consistent with the site observations, additional data, and photographs included in Addendum 2. Differences in other boring log data may be a result of drilling method and do not appear to reflect site observations. This clarification supersedes the clarification issued under Addendum No. 2.

Q3 Our segmented retaining wall system does not require geogrid. Must it still be furnished?

A3 Yes. The geogrid is called to provide additional stability to the roadway.



++ END OF ADDENDUM 3 ++

BARTON & LOGUIDICE, D.P.C.

A handwritten signature in blue ink, appearing to read "Eric A. Pond", written over a horizontal line.

Eric A. Pond, P.E.
Senior Vice-President

GBK/tlh
Attachments

ADDENDUM 3

Watkins-Montour Regional Wastewater Treatment Facility
Contract No. 2, Regional Wastewater Treatment Facility
CWSRF Project No. C8-6423-03-00

EMAIL TRANSMISSION – RETURN RECEIPT REQUESTED

PLEASE ACKNOWLEDGE BY RETURN EMAIL
(jfelber@bartonandloguidice.com)

Signature: _____ (*Robert Stanton*)

Date: February 7th, 2018

Title: Director of Marketing

Company: Streeter Associates, Inc.